

NE 1/4 S26, T2N, R64W, 6th PM
SHOWN VICINITY MAP TAKEN FROM USGS QUAD - KEENESBURG 40104-A5

VICINITY MAP
1" = 1,000'

LEGAL DESCRIPTION

LOT 2 OF MARKET STREET BUSINESS PARK SUBDIVISION
PART OF THE NORTHWEST 1/4 OF SECTION 26, TOWNSHIP 2 NORTH, RANGE 64 WEST OF THE 6TH P.M., TOWN OF
KEENESBURG, COUNTY OF WELD, STATE OF COLORADO

BASIS OF BEARING & PROJECT BENCHMARK

BASIS OF BEARING: THE NORTH LINE OF THE NORTHWEST 1/4 OF SECTION 26, TOWNSHIP 2 NORTH, RANGE 64 WEST OF
THE 6TH P.M., IN WELD COUNTY, COLORADO IS ASSUMED TO BEAR SOUTH 89°59'30" EAST, AS MONUMENTED HEREON, WITH
ALL BEARINGS CONTAINED HEREON RELATIVE THERETO.

PROJECT BENCHMARK: COLORADO DEPARTMENT OF TRANSPORTATION CONTROL POINT "CP 3892 / MP 38.92" 3 1/4"
ALUMINUM CAP IN THE WEST CENTER MEDIAN OF INTERSTATE 76 AT KEENESBURG EXIT. ELEVATION 1525.646 METERS OR
5005.40 FEET (NAVD 1988).

SITE BENCHMARK: WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE
IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF
THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39
FEET (NAVD 1988)

REVISIONS	SHEET	INDEX:
0	1	COVER SHEET
0	2	EXISTING CONDITIONS & DEMO PLAN
0	3	EXISTING CONDITIONS & DEMO PLAN W/ AERIAL
0	4	HORIZONTAL CONTROL PLAN
0	5	SITE PLAN
0	6	VEHICLE TRACKING - FIRE
0	7	VEHICLE TRACKING - GARBAGE
0	8	UTILITY PLAN
0	9	WATERLINE SERVICE DETAILS
0	10	SANITARY SERVICE PLAN & PROFILE
0	11	FIRE HYDRANT PLAN & PROFILE
0	12	GRADING PLAN
0	13	GRADING DETAILS
0	14	FINAL DRAINAGE PLAN
0	15	TOWN OF KEENESBURG DETAILS
0	16	CDOT DETAILS
0	17	CDOT DETAILS
0	18	INITIAL GESC PLAN
0	19	INTERIM GESC PLAN
0	20	FINAL GESC PLAN
0	21	GESC DETAILS
0	22	GESC DETAILS
0	23	GESC DETAILS
0	24	GESC DETAILS
0	25	GESC DETAILS
0	26	LANDSCAPE PLAN
0	27	LANDSCAPE DETAILS
0	28	BUILDING RENDERINGS
0	PH1	PHOTOMETRIC PLAN
0	PH2	PHOTOMETRIC DETAILS

SITE PLAN FOR:

HIGH PLAINS BANK -
LOT 2 MARKET STREET
BUSINESS PARK
WELD CNTY RD 18 & MARKET ST
KEENESBURG, CO

PREPARED FOR:

DBSI+CFM
BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext.233

APPROVED BY:

DBSI
BRIAN SILVESTER

DATE



WESTERN ENGINEERING CONSULTANTS, INC, LLC
CHADWIN F. COX, P.E.

0 INITIAL RELEASE FOR REVIEW:

JUNE 25, 2021

OWNER HIGH PLAINS BANK CONTACT: SAM CREIGHTON (915)207-6871	DEVELOPER DBSI+CFM CONTACT: BRIAN SILVESTER 6950 W MORELOS PL CHANDLER, AZ 85226 (602)264-7263	TOWN OF KEENESBURG CONTACT: TODD HODGES 140 S. MAIN STREET KEENESBURG, CO 80643 PHONE: (303)732-4281	SOUTHEAST WELD FIRE PROTECTION DISTRICT CONTACT: THOMAS BEACH 65 E. GANDY AVENUE KEENESBURG, CO 80643 PHONE: (303) 732-4203	ELECTRIC UTILITY UNITED POWER BRIGHTON HEADQUARTERS OFFICE 500 COOPERATIVE WAY BRIGHTON, CO 80603 (303)637-1300
--	---	--	--	--




UNCC
CALL BEFORE
YOU DIG

811
Utility Notification
Center of Colorado
Administrative Office
16351 Table Mountain Parkway
Golden, Colorado 80403
Office: 303-232-1991 Fax: 303-234-1712
Toll-Free: 1-800-922-1987

CALL 2-BUSINESS DAYS IN ADVANCE
BEFORE YOU DIG, GRADE, OR EXCAVATE
FOR THE MARKING OF UNDERGROUND
MEMBER UTILITIES.

PREPARED BY:




WESTERN ENGINEERING CONSULTANTS, inc. LLC
127 SOUTH DENVER AVE, FORT LUPTON CO 80621
720-685-9951 PH, 720-294-1330 FAX, email@westerneci.com

PROJECT NO: 00-0355-002-00
INITIAL PLAN RELEASE: June 25, 2021
SHEET: 1 of 28

TOWN OF KEENESBURG APPROVAL	
THESE DRAWINGS FOR HIGH PLAINS BANK - LOT 2 MARKET STREET BUSINESS PARK HAVE BEEN REVIEWED BY THE TOWN OF KEENESBURG AND ARE APPROVED FOR CONSTRUCTION.	
MAYOR	DATE
ATTEST: TOWN CLERK	DATE
TOWN ENGINEER	DATE

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 02-EXCON, 6/25/2021 10:34:08 PM, DWG To PDF.pc3



THIS SHEET

KEY MAP

SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE EXISTING CONDITIONS AND DEMO PLAN PLAN FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE EXISTING UNLESS NOTED AS PROPOSED.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, FINAL PLAT DATED AUGUST 14, 2020, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY AC 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

45 DEG BEND	THRUST BLOCK TB
22.5 DEG BEND	GATE VALVE GV
RESTRAINED PLUG	CURB STOP
RESTRAINED TEE	PIPE CROSSING
WATER METER	MANHOLE
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION
FIRE HYDRANT	ROOF DRAIN
RESTRAINED VALVE	
EXISTING CONC	PROPOSED GRAVEL
EXISTING ASPHALT	PROPOSED CONC
	PROPOSED ASPHALT

LINETYPE LEGEND

LOT / PROPERTY / SECTION LINE	PROPOSED SANITARY LINE
RIGHT OF WAY LINE	PROPOSED SANITARY SERVICE
EASEMENT	PROPOSED STORM LINE
SETBACK	PROPOSED WATER LINE
TO BE ABANDONED LOT LINE	PROPOSED WATER SERVICE
EXISTING BUILDING, CURB	PROPOSED GAS LINE
EDGE OF ASPHALT or GRAVEL RD	PROPOSED ELECTRIC LINE
CHAINLINK FENCE	PROPOSED TELEPHONE LINE
WIRE FENCE	
POND WQ W/S	
SWALE	
EXISTING OVERHEAD ELEC	
EXISTING ELECTRICAL LINE	
EXISTING STORM LINE	
EXISTING SANITARY LINE	
EXISTING WATER LINE	
EXISTING GAS LINE	
EXISTING FIBER OPTIC LINE	
EXISTING TELEPHONE LINE	

ONLY VALID FOR CONSTRUCTION
SCALE & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02


DOC CON #
0002-EXCON

SHEET
2 OF 28

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 03-EXCON W AERIAL, 6/25/2021 10:34:10 PM, DWG To PDF.pc3



KEY MAP SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE EXISTING CONDITIONS AND DEMO PLAN WITH AERIAL FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE EXISTING UNLESS NOTED AS PROPOSED.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, FINAL PLAT DATED AUGUST 14, 2020, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY AC 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

- | | |
|------------------|---------------------------|
| 41 45 DEG BEND | THRUST BLOCK TB |
| 41 22.5 DEG BEND | GATE VALVE GV |
| RESTRAINED PLUG | CURB STOP |
| RESTRAINED TEE | PIPE CROSSING |
| WATER METER | MANHOLE |
| RESTRAINED CROSS | MANHOLE W/ FLOW DIRECTION |
| FIRE HYDRANT | RD ROOF DRAIN |
| RESTRAINED VALVE | |

- | | |
|------------------|------------------|
| EXISTING CONC | PROPOSED GRAVEL |
| EXISTING ASPHALT | PROPOSED CONC |
| | PROPOSED ASPHALT |

LINETYPE LEGEND

- | | |
|-----|-------------------------------|
| --- | LOT / PROPERTY / SECTION LINE |
| --- | RIGHT OF WAY LINE |
| --- | EASEMENT |
| --- | SETBACK |
| --- | TO BE ABANDONED LOT LINE |
| --- | EXISTING BUILDING, CURB |
| --- | EDGE OF ASPHALT or GRAVEL RD |
| --- | CHAINLINK FENCE |
| --- | WIRE FENCE |
| --- | POND WQ W/S |
| --- | SWALE |
| --- | EXISTING OVERHEAD ELEC |
| --- | EXISTING ELECTRICAL LINE |
| --- | EXISTING STORM LINE |
| --- | EXISTING SANITARY LINE |
| --- | EXISTING WATER LINE |
| --- | EXISTING GAS LINE |
| --- | EXISTING FIBER OPTIC LINE |
| --- | EXISTING TELEPHONE LINE |
| --- | PROPOSED SANITARY LINE |
| --- | PROPOSED SANITARY SERVICE |
| --- | PROPOSED STORM LINE |
| --- | PROPOSED WATER LINE |
| --- | PROPOSED WATER SERVICE |
| --- | PROPOSED GAS LINE |
| --- | PROPOSED ELECTRIC LINE |
| --- | PROPOSED TELEPHONE LINE |

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

EX. CON. & DEMO W/ AERIAL
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SCALE & ORIGINAL SIGNATURE
ARE ON EACH SHEET


INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02

DOC CON #
0003-EXCON AE

SHEET
3 OF 28


\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 04-HZ-CTRL, 6/25/2021, 10:34:16 PM, DWG to PDF, p3



PROPERTY LINE CURVE TABLE					
CURVE #	ARC LENGTH	RADIUS	DELTA ANGLE	CHORD BEARING	CHORD LENGTH
C19	45.42	29.00	89°44'06"	S45°41'44"E	40.92

PROPERTY CORNER POINT TABLE		
DESCRIPTION	NORTHING	EASTING
PC-NE-1	1287155.3105	3274551.5869
PC-NE-2	1287126.7311	3274580.8690
PC-NW	1287152.7443	3274290.5088
PC-SE	1287002.9618	3274582.6580
PC-SW	1286998.7712	3274292.7345

PROPERTY LINE TABLE		
LINE #	BEARING	DISTANCE
L24	S89°10'19"W	289.93
L25	N00°49'41"W	153.99
L26	N89°26'13"E	261.09
L27	S00°49'10"E	123.78



KEY MAP SCALE 1" = 300'

LINE TABLE		
LINE #	BEARING	DISTANCE
L1	N89°10'19"E	244.65
L2	N00°49'16"W	108.81
L3	S89°26'13"W	86.17
L4	S89°10'19"W	19.43
L5	S00°49'41"E	10.19
L6	N89°10'19"E	6.50
L7	S00°49'41"E	54.09
L8	S89°10'19"W	86.46
L9	N00°47'36"W	114.90
L10	N00°48'20"W	70.18
L11	N89°26'13"E	69.65
L12	S00°35'48"E	0.34
L13	S89°10'40"W	18.00
L14	S00°49'20"E	65.00
L15	N89°10'40"E	18.00
L16	S00°49'20"E	1.00
L17	S89°09'41"W	12.22
L18	N00°49'41"W	18.00
L19	S89°10'19"W	50.00
L20	S00°49'41"E	18.00
L21	S89°10'26"W	3.00
L22	N00°47'31"W	36.00
L23	S00°47'31"E	36.00

CURVE TABLE					
CURVE #	ARC LENGTH	RADIUS	DELTA ANGLE	CHORD BEARING	CHORD LENGTH
C1	15.71	10.00	90°02'03"	N44°09'17"E	14.15
C2	44.68	28.50	89°49'52"	N45°38'51"W	40.25
C3	7.22	10.12	40°52'47"	S68°43'55"W	7.07
C4	7.22	10.12	40°52'47"	S68°43'55"W	7.07
C5	4.63	2.00	132°30'14"	S24°32'47"E	3.66
C6	40.83	55.00	42°32'02"	S20°26'19"W	39.90
C7	7.07	4.50	90°00'00"	S44°10'19"W	6.36
C8	15.71	10.00	90°00'00"	N45°49'41"W	14.14
C9	23.63	15.00	90°15'54"	N44°18'16"E	21.26
C10	7.07	4.50	89°57'58"	S45°34'48"E	6.36
C11	3.14	2.00	90°00'00"	S44°10'40"W	2.83
C12	3.14	2.00	90°00'00"	S45°49'20"E	2.83
C13	23.56	15.00	89°59'31"	S44°10'26"W	21.21
C14	3.14	2.00	90°00'38"	N45°50'00"W	2.83
C15	3.14	2.00	90°00'07"	S44°10'22"W	2.83
C16	7.85	5.00	90°00'07"	N45°49'45"W	7.07
C17	6.28	2.00	180°00'05"	S89°12'27"W	4.00
C18	6.28	2.00	180°00'00"	N89°12'29"E	4.00

BUILDING POINT TABLE		
DESCRIPTION	NORTHING	EASTING
BLDG-01	1287057.6525	3274457.1364
BLDG-02	1287058.4042	3274509.1326
BLDG-03	1287067.7959	3274508.9966
BLDG-04	1287068.0378	3274514.1979
BLDG-05	1287082.3696	3274513.9907
BLDG-06	1287082.3377	3274511.7784
BLDG-07	1287090.5272	3274511.6600
BLDG-08	1287090.4454	3274505.9982
BLDG-09	1287118.3594	3274505.5947
BLDG-10	1287117.7405	3274462.7765
BLDG-11	1287094.9926	3274463.1054
BLDG-12	1287094.8985	3274456.5980

UTILITIES POINT TABLE		
DESCRIPTION	NORTHING	EASTING
EL-01	1287142.2002	3274434.8309
EL-02	1287117.7405	3274462.7765
FO-01	1287145.6285	3274463.7806
FO-02	1287117.7608	3274464.1834
FP-01	1287195.3483	3274407.6237
FP-02	1287088.0979	3274409.1741
SS-01	1287019.2603	3274326.4292
SS-02	1287019.5493	3274346.4272
SS-03	1287020.5719	3274417.1691
SS-04	1287059.6234	3274455.1077
SS-05	1287059.6523	3274457.1075
T-01	1287149.6670	3274468.7227
T-02	1287117.8331	3274469.1829
WAS-01	1287009.2710	3274327.2451
WAS-02	1287011.2013	3274460.7909
WAS-03	1287032.6987	3274460.4802
WAS-04	1287057.6957	3274460.1189


HORIZONTAL CONTROL PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO


ONLY VALID FOR CONSTRUCTION
IF SEAL & SIGNATURE ARE ON EACH SHEET
INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0004-HZ CTRL
SHEET
4 OF 28

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330
Western Engineering Consultants, Inc LLC

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 05-SITE, 6/25/2021 10:34:22 PM, DWG To PDF, PC3



SETBACK DATA TABLE	
PROPERTY LINE	BUILDING SETBACK
FRONT	25.00'
REAR	25.00'
SIDE*	10.00'



KEY MAP SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE SITE PLAN FOR HIGH PLAINS BANK - LOT 2 MARKET ST BUSINESS PARK.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

41 45 DEG BEND	THRUST BLOCK TB
41 22.5 DEG BEND	GATE VALVE GV
RESTRAINED PLUG	CURB STOP
RESTRAINED TEE	PIPE CROSSING
WATER METER	MANHOLE
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION
FIRE HYDRANT	ROOF DRAIN RD
RESTRAINED VALVE	
EXISTING CONC	PROPOSED GRAVEL
EXISTING ASPHALT	PROPOSED CONC
	PROPOSED ASPHALT

LINETYPE LEGEND

---	LOT / PROPERTY / SECTION LINE
---	RIGHT OF WAY LINE
---	EASEMENT
---	SETBACK
---	TO BE ABANDONED LOT LINE
---	EXISTING BUILDING, CURB
---	EDGE of ASPHALT or GRAVEL RD
---	CHAINLINK FENCE
---	WIRE FENCE
---	POND WQ W/S
---	SWALE
---	EXISTING OVERHEAD ELEC
---	EXISTING ELECTRICAL LINE
---	EXISTING STORM LINE
---	EXISTING SANITARY LINE
---	EXISTING WATER LINE
---	EXISTING GAS LINE
---	EXISTING FIBER OPTIC LINE
---	EXISTING TELEPHONE LINE
---	PROPOSED SANITARY LINE
---	PROPOSED SANITARY SERVICE
---	PROPOSED STORM LINE
---	PROPOSED WATER LINE
---	PROPOSED WATER SERVICE
---	PROPOSED GAS LINE
---	PROPOSED ELECTRIC LINE
---	PROPOSED TELEPHONE LINE

LOT DATA TABLE				
DESCRIPTION	AREA	AREA (ac)	EXISTING %	PROPOSED %
LOT	44,276 SF	1.02	100 %	100 %
PROPOSED BUILDINGS	2,997 SF	0.07	6.77 %	
TOTAL BUILDINGS	2,997 SF	0.07		6.77 %
PROPOSED CONCRETE	3,703 SF	0.09	8.36 %	
EX CONCRETE TO BE REMOVED	100 SF	0.00	0.23 %	
TOTAL CONCRETE	3,603 SF	0.08		8.14 %
PROPOSED ASPHALT	15,665 SF	0.36	35.38 %	
EX ASPHALT TO BE REMOVED	0 SF	0.00	0.00 %	
TOTAL ASPHALT	15,665 SF	0.36		35.38 %
EX GRAVEL TBR/REGRADED	0 SF	0.00	0.00 %	
PROPOSED GRAVEL	0 SF	0.00		0.00 %
TOTAL GRAVEL	0 SF	0.00		0.00 %
EXISTING LANDSCAPE AREA	38,954 SF	0.89	87.98 %	
PROPOSED LANDSCAPE AREA	22,010 SF	0.51		49.71 %

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

SITE PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

DigiSafely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC


PROJECT NO.
01-0355.001.02
DOC CON #
0005-FUT SITE

SHEET
5 OF 28

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\Drawg\CD\0355-001-02-WEC-SPR.dwg, 06-VTC FIRE 6/25/2021 10:34:27 PM, DWG to PDF, pc3


SETBACK DATA TABLE	
PROPERTY LINE	BUILDING SETBACK
FRONT	25.00'
REAR	25.00'
SIDE*	10.00'

FIRE TRACK



127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC



KEY MAP
SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE VEHICLE TRACKING - FIRE PLAN FOR HIGH PLAINS BANK - LOT 2 MARKET ST BUSINESS PARK.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988).


ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND	
45 DEG BEND	THRUST BLOCK TB
22.5 DEG BEND	GATE VALVE GV
RESTRAINED PLUG	CURB STOP
RESTRAINED TEE	PIPE CROSSING
WATER METER	MANHOLE
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION
FIRE HYDRANT	ROOF DRAIN RD
RESTRAINED VALVE	
EXISTING CONC	PROPOSED GRAVEL
EXISTING ASPHALT	PROPOSED CONC
	PROPOSED ASPHALT

LINETYPE LEGEND	
---	LOT / PROPERTY / SECTION LINE
---	RIGHT OF WAY LINE
---	EASEMENT
---	SETBACK
---	TO BE ABANDONED LOT LINE
---	EXISTING BUILDING, CURB
---	EDGE of ASPHALT or GRAVEL RD
---	CHAINLINK FENCE
---	WIRE FENCE
---	POND WQ W/S
---	SWALE
---	EXISTING OVERHEAD ELEC
---	EXISTING ELECTRICAL LINE
---	EXISTING STORM LINE
---	EXISTING SANITARY LINE
---	EXISTING WATER LINE
---	EXISTING GAS LINE
---	EXISTING FIBER OPTIC LINE
---	EXISTING TELEPHONE LINE
---	PROPOSED SANITARY LINE
---	PROPOSED SANITARY SERVICE
---	PROPOSED STORM LINE
---	PROPOSED WATER LINE
---	PROPOSED WATER SERVICE
---	PROPOSED GAS LINE
---	PROPOSED ELECTRIC LINE
---	PROPOSED TELEPHONE LINE



LOT DATA TABLE				
DESCRIPTION	AREA	AREA (ac)	EXISTING %	PROPOSED %
LOT	44,276 SF	1.02	100 %	100 %
PROPOSED BUILDINGS	2,997 SF	0.07	6.77 %	
TOTAL BUILDINGS	2,997 SF	0.07		6.77 %
PROPOSED CONCRETE	3,703 SF	0.09	8.36 %	
EX CONCRETE TO BE REMOVED	100 SF	0.00	0.23 %	
TOTAL CONCRETE	3,603 SF	0.08		8.14 %
PROPOSED ASPHALT	15,665 SF	0.36	35.38 %	
EX ASPHALT TO BE REMOVED	0 SF	0.00	0.00 %	
TOTAL ASPHALT	15,665 SF	0.36		35.38 %
EX GRAVEL TBR/REGRADED	0 SF	0.00	0.00 %	
PROPOSED GRAVEL	0 SF	0.00		0.00 %
TOTAL GRAVEL	0 SF	0.00		0.00 %
EXISTING LANDSCAPE AREA	38,954 SF	0.89	87.98 %	
PROPOSED LANDSCAPE AREA	22,010 SF	0.51		49.71 %

VEHICLE TRACKING - FIRE
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2

TOWN of KEENESBURG, WELD COUNTY, COLORADO


Dig Safely.
CALL UNCC
THREE WORKING DAYS BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SCALE & DESIGN SIGNATURE ARE ON EACH SHEET




INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02
DOC CON #
0006-VTC FIRE
SHEET
6 OF 28

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 08-UTILITY, 6/25/2021 10:34:40 PM, DWG To PDF, pc3



\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 09-WAS.DTL, 6/25/2021 10:34:45 PM, DWG to PDF.pc3



NOTES

THIS PLAN IS INTENDED AS THE GRADING PLAN FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND	
	45 DEG BEND
	22.5 DEG BEND
	RESTRAINED PLUG
	RESTRAINED TEE
	WATER METER
	RESTRAINED CROSS
	FIRE HYDRANT
	RESTRAINED VALVE
	THRUST BLOCK
	GATE VALVE
	CURB STOP
	PIPE CROSSING
	MANHOLE
	MANHOLE W/ FLOW DIRECTION
	ROOF DRAIN
	PROPOSED GRAVEL
	EXISTING CONC
	PROPOSED CONC
	EXISTING ASPHALT
	PROPOSED ASPHALT

LINETYPE LEGEND	
	LOT / PROPERTY / SECTION LINE
	RIGHT OF WAY LINE
	EASEMENT
	SETBACK
	TO BE ABANDONED LOT LINE
	EXISTING BUILDING, CURB
	EDGE of ASPHALT or GRAVEL RD
	CHAINLINK FENCE
	WIRE FENCE
	POND WQ W/S
	SWALE
	EXISTING OVERHEAD ELEC
	EXISTING ELECTRICAL LINE
	EXISTING STORM LINE
	EXISTING SANITARY LINE
	EXISTING WATER LINE
	EXISTING GAS LINE
	EXISTING FIBER OPTIC LINE
	EXISTING TELEPHONE LINE
	PROPOSED SANITARY LINE
	PROPOSED SANITARY SERVICE
	PROPOSED STORM LINE
	PROPOSED WATER LINE
	PROPOSED WATER SERVICE
	PROPOSED GAS LINE
	PROPOSED ELECTRIC LINE
	PROPOSED TELEPHONE LINE

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

DATE	BY	REVISION	INITIAL	REUSE
06/25/21	CFC			

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext. 233

WATERLINE SERVICE DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE ARE ON EACH SHEET


INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02



DOC CON #
0009-WAS DTL

SHEET
9 OF 28

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\DWG\CD\0355-001-02-WEC-SPR.dwg, 10:54N P86, 6/25/2021 10:34:49 PM, DWG to PDF, P3



LOT 1
1.98 ac



THIS SHEET

KEY MAP

SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE GRADING PLAN FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

45 DEG BEND	THRUST BLOCK TB
22.5 DEG BEND	GATE VALVE GV
RESTRAINED PLUG	CURB STOP
RESTRAINED TEE	PIPE CROSSING
WATER METER	MANHOLE
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION
FIRE HYDRANT	ROOF DRAIN
RESTRAINED VALVE	

EXISTING CONC	PROPOSED GRAVEL
EXISTING ASPHALT	PROPOSED CONC
	PROPOSED ASPHALT

LINETYPE LEGEND

SA	SA	PROPOSED SANITARY LINE
SS	SS	PROPOSED SANITARY SERVICE
ST	ST	PROPOSED STORM LINE
WA	WA	PROPOSED WATER LINE
WAS	WAS	PROPOSED WATER SERVICE
GA	GA	PROPOSED GAS LINE
EL	EL	PROPOSED ELECTRIC LINE
T	T	PROPOSED TELEPHONE LINE

LOT / PROPERTY / SECTION LINE
RIGHT OF WAY LINE
EASEMENT
SETBACK
TO BE ABANDONED LOT LINE
EXISTING BUILDING, CURB
EDGE OF ASPHALT or GRAVEL RD
CHAINLINK FENCE
WIRE FENCE
POND WQ W/S
SWALE
EXISTING OVERHEAD ELEC
EXISTING ELECTRICAL LINE
EXISTING STORM LINE
EXISTING SANITARY LINE
EXISTING WATER LINE
EXISTING GAS LINE
EXISTING FIBER OPTIC LINE
EXISTING TELEPHONE LINE

Sanitary Service P&P
Market Street Business
Park Subdivision - Lot 2

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO


ONLY VALID FOR CONSTRUCTION
IF SEAL & SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC



PROJECT NO.
01-0355.001.02
DOC CON #
0010-SAN SVC
SHEET
10 OF 28

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC



POTHOLE/CONNECTION NOTE
CONTRACTOR TO POTHOLE ALL CONNECTION POINTS 5 DAYS PRIOR TO CONSTRUCTION AND NOTIFY WESTERN ENGINEERING CONSULTANTS (WEC) OF ANY DISCREPANCIES FROM DESIGN.




4.5' MIN. WATERLINE COVER,
5.0' MIN. FIRE LINE COVER

JOINT DEFLECTION
SHALL NOT EXCEED 1°

ALL WATER LINE VALVES, BENDS,
AND FITTINGS SHALL BE RESTRAINED
AND THRUST BLOCKS INSTALLED.
SEE ALSO JOINT RESTRAINT TABLE
THIS SHEET.

ALL FIRELINE JOINTS AND FITTINGS
TO BE RESTRAINED WITH MEGALUGS
OR APPROVED EQUAL IN ADDITION
TO THRUST BLOCK INSTALLATION.

JOINT RESTRAINT TABLE									
(Using Test pressure 200 psi, soil type Sandy Clay per Geotech Report)									
All values below are feet in each direction unless otherwise noted									
22.5	45	90	8* Tee	8* Tee	45 V bend	22.5 V bend	11.25 V bend	8*3 Reduction	Dead End
9	18	42	14	9/49 up, 12 lower	24 up, 6 lower	12 up, 3 lower		76	94



NOTES

THIS PLAN IS INTENDED AS THE GRADING PLAN FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AND ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND			
45 DEG BEND	THRUST BLOCK TB	PROPOSED GRAVEL	
22.5 DEG BEND	GATE VALVE GV	PROPOSED CONC	
RESTRAINED PLUG	CURB STOP	PROPOSED ASPHALT	
RESTRAINED TEE	PIPE CROSSING		
WATER METER	MANHOLE		
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION		
FIRE HYDRANT	ROOF DRAIN		
RESTRAINED VALVE			

LINETYPE LEGEND			
---	LOT / PROPERTY / SECTION LINE	---	---
---	RIGHT OF WAY LINE	---	---
---	EASEMENT	---	---
---	SETBACK	---	---
---	TO BE ABANDONED LOT LINE	---	---
---	EXISTING BUILDING, CURB	---	---
---	EDGE of ASPHALT or GRAVEL RD	---	---
---	CHAINLINK FENCE	---	---
---	WIRE FENCE	---	---
---	POND WQ W/S	---	---
---	SWALE	---	---
---	EXISTING OVERHEAD ELEC	---	---
---	EXISTING ELECTRICAL LINE	---	---
---	EXISTING STORM LINE	---	---
---	EXISTING SANITARY LINE	---	---
---	EXISTING WATER LINE	---	---
---	EXISTING GAS LINE	---	---
---	EXISTING FIBER OPTIC LINE	---	---
---	EXISTING TELEPHONE LINE	---	---
SA	SA	PROPOSED SANITARY LINE	
SS	SS	PROPOSED SANITARY SERVICE	
ST	ST	PROPOSED STORM LINE	
WA	WA	PROPOSED WATER LINE	
WAS	WAS	PROPOSED WATER SERVICE	
GA	GA	PROPOSED GAS LINE	
EL	EL	PROPOSED ELECTRIC LINE	
T	T	PROPOSED TELEPHONE LINE	

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

DATE: 06/25/21 BY: CFC

REVISION: INITIAL REUSE: NO

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext. 233

FIRE HYDRANT P&P
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO


Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
* SEE * DESIGN * SIGNATURE
ARE ON EACH SHEET


INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02
DOC CON #
0011-FH P&P

SHEET
11 OF 28



HIGH PLAINS BANK - LOT 2 EARTHWORK SUMMARY				
Description	Area (sq. ft.)	Thickness (inches)	Volume (cubic ft)	Volume (cubic yds)
ASPHALT	15,198	-8.0	-10,132	(375)
CONCRETE (BUILDING)	2,997	-6.0	-1,499	(56)
CONCRETE (MISC)	2,087	-6.0	-1,043	(39)
OVER-EX SOIL REPLACEMENT	0	0	0	-
A TOTAL IMPORT (HARDSCAPE)	20,282 sft		-12,674	(469) A
Net Adjusted Hardscape Area	0.47 ac			
	1.01 ac			
B1 EG to FG Surface to Surface net cut required (cy)				702
B2 EG to FG Surface to Surface net (fill) required (cy)				(253) B
B Surface to Surface net cut (fill) required (cy) after 10% fill shrinkage				449 B
(B-A) Net Excess or (Shortage) cy needed in order to balance				918
Net adjustment to balance + raise, (lower) in feet over area noted above				0.56
% Unbalanced				205%
Assumed Site Stripping's under new asphalt, conc, bldg (4" over 45,973 sf)				250
Assumed Overall Site Stripping's (4" over 9.95 ac) (433422 sf)				543
Summary B includes assumed 10% shrinkage of fill material				
Additional import may be necessary to achieve stabilization.				
Additional import may be required and an excess material condition could occur.				
No overexcavation, foundation excavation, or buried utility export, has been included in this table.				
Not all landscape hardscape areas have been accounted for in this table.				



NOTES

THIS PLAN IS INTENDED AS THE GRADING PLAN FOR MARKET ST BUSINESS PARK - LOT 2.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

45 DEG BEND	THRUST BLOCK TB
22.5 DEG BEND	GATE VALVE
RESTRAINED PLUG	CURB STOP
RESTRAINED TEE	PIPE CROSSING
WATER METER	MANHOLE
RESTRAINED CROSS	MANHOLE W/ FLOW DIRECTION
FIRE HYDRANT	ROOF DRAIN
RESTRAINED VALVE	

EXISTING CONC	PROPOSED GRAVEL
EXISTING ASPHALT	PROPOSED CONC
	PROPOSED ASPHALT

LINETYPE LEGEND

LOT / PROPERTY / SECTION LINE	RIGHT OF WAY LINE
EASEMENT	SETBACK
TO BE ABANDONED LOT LINE	EXISTING BUILDING, CURB
EDGE of ASPHALT or GRAVEL RD	CHAINLINK FENCE
WIRE FENCE	POND WQ W/S
SWALE	EXISTING OVERHEAD ELEC
EXISTING ELECTRICAL LINE	EXISTING STORM LINE
EXISTING SANITARY LINE	EXISTING WATER LINE
EXISTING GAS LINE	EXISTING FIBER OPTIC LINE
EXISTING TELEPHONE LINE	

SA	SA	PROPOSED SANITARY LINE
SS	SS	PROPOSED SANITARY SERVICE
ST	ST	PROPOSED STORM LINE
WA	WA	PROPOSED WATER LINE
WAS	WAS	PROPOSED WATER SERVICE
GA	GA	PROPOSED GAS LINE
EL	EL	PROPOSED ELECTRIC LINE
T	T	PROPOSED TELEPHONE LINE

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

DATE: 06/25/21
BY: CFC
REVISION: 06/25/21
INITIAL: BRS
NO: 0355-001-02

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602) 264-7263 ext. 233


GRADING PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO


























































ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET


INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355.001.02
DOC CON #
0012-GRADE
SHEET
12 OF 28



KEY MAP SCALE 1" = 300'

NOTES	
THIS PLAN IS INTENDED AS THE GRADING PLAN FOR MARKET ST BUSINESS PARK – LOT 2.	
ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.	
IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.	
SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY – DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019. WACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.	
SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.	
SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY AC'D 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)	
ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS – SPECIFICALLY PER SAME SURVEY NOTED ABOVE.	
NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.	
BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)	
SYMBOL LEGEND	
 45 DEG BEND  22.5 DEG BEND  RESTRAINED PLUG  RESTRAINED TEE  WATER METER  RESTRAINED CROSS  FIRE HYDRANT  RESTRAINED VALVE	 THRUST BLOCK TB  GATE VALVE GV  CURB STOP  PIPE CROSSING  MANHOLE  MANHOLE W/ FLOW DIRECTION  RD
 EXISTING CONC  EXISTING ASPHALT	 PROPOSED GRAVEL  PROPOSED CONC  PROPOSED ASPHALT
LINETYPE LEGEND	
 LOT / PROPERTY / SECTION LINE  RIGHT OF WAY LINE  EASEMENT  SETBACK  TO BE ABANDONED LOT LINE  EXISTING BUILDING, CURB  EDGE OF ASPHALT or GRAVEL RD  CHAINLINK FENCE  WIRE FENCE  POND WQ W/S  SWALE  EXISTING OVERHEAD ELEC  EXISTING ELECTRICAL LINE  EXISTING STORM LINE  EXISTING SANITARY LINE  EXISTING WATER LINE  EXISTING GAS LINE  EXISTING FIBER OPTIC LINE  EXISTING TELEPHONE LINE  SA  SS  WAS  EL  T  SA  SS  WAS  EL  T	 PROPOSED SANITARY LINE  PROPOSED SANITARY SERVICE  PROPOSED STORM LINE  PROPOSED WATER LINE  PROPOSED WATER SERVICE  PROPOSED GAS LINE  PROPOSED ELECTRIC LINE  PROPOSED TELEPHONE LINE

		127 S. DENVER AVE FT. LUTON, CO 80621 www.westernec.com email@westernec.com (720) 685-4951 FAX (720) 234-1130	
Western Engineering Consultants, Inc LLC			
NO.	REVISION	DATE	BY
0	INITIAL RELEASE	06/29/21	CFC
17351 + CFM CONTACT: BRIAN SILVESTER 6950 W MORELOS PL CHANDLER, AZ 85226 (602)264-7263 ext. 233			
GRADING DETAILS MARKET STREET BUSINESS PARK SUBDIVISION - LOT 2 TOWN OF KEENESBURG, WELD COUNTY, COLORADO			
Dig Safely. CALL UNCC 811 www.unc.org UTILITY NOTIFICATION CENTER OF COLORADO			
ONLY VALID FOR CONSTRUCTION * SEAL & ORIGINAL SIGNATURE ARE ON EACH SHEET			
INITIAL PLAN RELEASE: 06/25/21 DESIGNED BY: CFC DRAWN BY: CFC CHECKED BY: CFC			
PROJECT NO 01-0355.001.02			
DOC CON # 0013-GRADE			
SHEET 13 OF 28			

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\Drawg\CD\0355-001-02-WEC-SPR.dwg, 14-DRNG, 6/25/2021 10:42:48 PM DWG To PDF.p3

DEVELOPED DRAINAGE LEGEND

B1

3.2 XX

XX

C5

C100

Area in Acres

PROPOSED DRAINAGE PATTERN

DEVELOPED BASIN

DESIGN POINT

Existing Drainage Pattern

L - INITIAL LENGTH

S - INTIAL SLOPE

L - TRAVEL LENGTH

S - TRAVEL SLOPE

* AVERAGE SLOPE INCLUDES ROOF SLOPE OF 8.33%

$L_i = L_i$


$S_i = S_i$

$L_t = L_t$

$S_t = S_t$


Developed Runoff Table - Market Street Business Park Subdivision						
BASIN	Impervious	C-YR	I	A	CIA(YR-DEVELOPED) cfs	DESIGN POINT
L2						
C ₂ (UDFCD 2018)	56.29	0.46	2.88	1.01	1.35 cfs	9
C ₅	56.29	0.49	3.83	1.01	1.91 cfs	
C ₁₀	56.29	0.55	4.74	1.01	2.63 cfs	
C ₁₀₀	56.29	0.71	8.94	1.01	6.43 cfs	

SETBACK DATA TABLE	
PROPERTY LINE	BUILDING SETBACK
FRONT	25.00'
REAR	25.00'
SIDE*	10.00'



127 S. DENVER AVE
FT. LUTON, CO 80621
www.westernecol.com
email@westernecol.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC



KEY MAP SCALE 1" = 300'

NOTES

THIS PLAN IS INTENDED AS THE SITE PLAN FOR HIGH PLAINS BANK - LOT 2 MARKET ST BUSINESS PARK.

ALL IMPROVEMENTS ARE PROPOSED UNLESS NOTED AS EXISTING.

IT IS THE OWNER AND/OR THE CONTRACTOR'S RESPONSIBILITY TO ATTAIN ALL APPROPRIATE PERMITS AND REVIEW APPROVALS FROM THE STATE OF COLORADO AND TOWN OF KEENESBURG RESPECTIVELY.

SEE "AS BUILT/BOUNDARY SURVEY" COMPLETED BY AMERICAN WEST LAND SURVEY - DATED MAY 24, 2006, UPDATED TOPOGRAPHY AND IMPROVEMENTS SURVEY DATED AUGUST 07, 2019, MACY ENTERPRISES AS-BUILTS, AND AS CONSTRUCTED CONDITIONS DRONE AERIAL SURVEY BY AMERICAN WEST LAND SURVEY AND WESTERN ENGINEERING CONSULTANTS DATED APRIL 13, 2021.

SEE COVER SHEET FOR PROJECT BASIS OF BEARING & LEGAL DESCRIPTION.

SITE BENCHMARK WAS ESTABLISHED BEING A 3" BRASS CAP IN CONCRETE LYING FIVE FEET WEST OF A CONCRETE IRRIGATION DITCH NEAR THE INTERSECTION OF COUNTY ROAD 18 AND NORTH CEDAR STREET, AND THIRTY FEET NORTH OF THE CENTERLINE OF COUNTY ROAD 18. STAMPED "NATIONAL GEODETIC SURVEY ACD 1" HAVING AN ELEVATION OF 5015.39 FEET (NAVD 1988)

ANY REFERENCE TO EASEMENTS, SURVEY POINTS, OR EXISTING UTILITIES AND FEATURES ARE BASED SOLELY FROM SURVEY INFORMATION PROVIDED BY OTHERS - SPECIFICALLY PER SAME SURVEY NOTED ABOVE.

NOT ALL UNCC UTILITY LOCATES HAVE BEEN PERFORMED. IT IS THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL UTILITIES ARE LOCATED AND SURVEY PROVIDED TO THE OWNER AND ENGINEER PRIOR TO CONSTRUCTION DRAWING RELEASE.

BUILDING SETBACKS FRONT/REAR = 25', SIDES = 10' PER ZONE DISTRICT HIGHWAY COMMERCIAL (CH)

SYMBOL LEGEND

45 DEG BEND

22.5 DEG BEND

RESTRAINED PLUG

RESTRAINED TEE

WATER METER

RESTRAINED CROSS

FIRE HYDRANT

RESTRAINED VALVE

THRUST BLOCK

GATE VALVE

CURB STOP

PIPE CROSSING

MANHOLE

MANHOLE W/ FLOW DIRECTION

ROOF DRAIN

PROPOSED GRAVEL

EXISTING CONC

EXISTING ASPHALT

PROPOSED CONC

PROPOSED ASPHALT

LINETYPE LEGEND

LOT / PROPERTY / SECTION LINE

RIGHT OF WAY LINE

EASEMENT

SETBACK

TO BE ABANDONED LOT LINE

EXISTING BUILDING, CURB

EDGE of ASPHALT or GRAVEL RD

CHAINLINK FENCE

WIRE FENCE

POND WQ W/S

SWALE

OHE

EL

SA

WA

GA

FO

SA

SS

ST

WA

WAS

GA

EL

T

EXISTING OVERHEAD ELEC

EXISTING ELECTRICAL LINE

EXISTING STORM LINE

EXISTING SANITARY LINE

EXISTING WATER LINE

EXISTING GAS LINE

EXISTING FIBER OPTIC LINE

EXISTING TELEPHONE LINE

PROPOSED SANITARY LINE

PROPOSED SANITARY SERVICE

PROPOSED STORM LINE

PROPOSED WATER LINE

PROPOSED WATER SERVICE

PROPOSED GAS LINE

PROPOSED ELECTRIC LINE

PROPOSED TELEPHONE LINE

LOT DATA TABLE				
DESCRIPTION	AREA	AREA (ac)	EXISITNG %	PROPOSED %
LOT	44,276 SF	1.02	100 %	100 %
PROPOSED BUILDINGS	2,997 SF	0.07	6.77 %	
TOTAL BUILDINGS	2,997 SF	0.07		6.77 %
PROPOSED CONCRETE	3,703 SF	0.09	8.36 %	
EX CONCRETE TO BE REMOVED	100 SF	0.00	0.23 %	
TOTAL CONCRETE	3,603 SF	0.08		8.14 %
PROPOSED ASPHALT	15,665 SF	0.36	35.38 %	
EX ASPHALT TO BE REMOVED	0 SF	0.00	0.00 %	
TOTAL ASPHALT	15,665 SF	0.36		35.38 %
EX GRAVEL TBR/REGRADED	0 SF	0.00	0.00 %	
PROPOSED GRAVEL	0 SF	0.00		0.00 %
TOTAL GRAVEL	0 SF	0.00		0.00 %
EXISTING LANDSCAPE AREA	38,954 SF	0.89	87.98 %	
PROPOSED LANDSCAPE AREA	22,010 SF	0.51		49.71 %

FINAL DRAINAGE PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21

DESIGNED BY: CFC



DRAWN BY: CFC

CHECKED BY: CFC

PROJECT NO.
01-0355.001.02

DOC CON #
0014-DRNG

SHEET
14 OF 28



CDOT DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC


PROJECT NO.
01-0355.001.02

DOC CON #
0017-CDOT DTLS




















SHEET
17 OF 28


127 S. DENVER AVE
FT. LUTPON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC




BMP LEGEND

	(CWA)	CONCRETE WASHOUT AREA
	(CF)	CONSTRUCTION FENCE
	(CM)	CONSTRUCTION MARKER
	(CIP)	CULVERT INLET PROTECTION
	(DC)	WIND EROSION & DUST CONTROL
	(DS)	DRAINAGE SWALE
	(GH)	GOOD HOUSEKEEPING PRACTICE
	(IP)	INLET PROTECTION
	(PS)	PERMANENT SEEDING
	(RS)	ROCK SOCK
	(SB)	SEDIMENT BASIN
	(SCL)	SEDIMENT CONTROL LOG
	(SF)	SILT FENCE
	(SS)	STREET SWEEPING VACUUMING
	(SSA)	STABILIZED STAGING AREA
	(SP)	STOCK PILE
	(TOP)	TEMPORARY OUTLET PROTECTION
	(VB)	VEGETATED BUFFER
	(VTC)	VEHICLE TRACKING CONTROL



KEY MAP

SCALE 1" = 300'



127 S. DENVER AVE
FT. LUPTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, inc LLC

7351 + CFM CONTACT: BRIAN SILVESTER 6950 W MORELOS PL CHANDLER, AZ 85226 (602)264-7263 ext. 233		REV. 12/18/01 INITIAL RELEASE	DATE: 06/25/01 BY: JFC
--	--	----------------------------------	---------------------------

INTERIM GESC PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET


INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC

PROJECT NO.
01-0355-001.02


DOC CON #
0019-INT GESC

SHEET
19 OF 28

\\WESERVER1\Share\0355_002_00-HIGH PLAINS BANK - Keenesburg\Drawg\CD\0355-001-02-WEC-SPR.dwg, 20-FIN GESC, 6/25/2021 10:35:33 PM, DWG to PDF, #3



BMP LEGEND		
	CWA	CONCRETE WASHOUT AREA
	CF	CONSTRUCTION FENCE
	CM	CONSTRUCTION MARKER
	CIP	CULVERT INLET PROTECTION
	DC	WIND EROSION & DUST CONTROL
	DS	DRAINAGE SWALE
	GH	GOOD HOUSEKEEPING PRACTICE
	IP	INLET PROTECTION
	PS	PERMANENT SEEDING
	RS	ROCK SOCK
	SB	SEDIMENT BASIN
	SCL	SEDIMENT CONTROL LOG
	SF	SILT FENCE
	SS	STREET SWEEPING VACUUMING
	SSA	STABILIZED STAGING AREA
	SP	STOCK PILE
	TOP	TEMPORARY OUTLET PROTECTION
	VB	VEGETATED BUFFER
	VTC	VEHICLE TRACKING CONTROL



127 S. DENVER AVE.
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc. LLC

NO.	REVISION	DATE	BY
1	INITIAL RELEASE	06/25/21	CFC

DOSI + CFM
CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602) 264-7263 ext. 233

FINAL GESC PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET
INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0020-FIN GESC
SHEET
20 OF 28

Earth Dikes and Drainage Swales (ED/DS) EC-10

Description

Earth dikes and drainage swales are temporary storm conveyance channels constructed either to divert runoff around slopes or to convey runoff to additional sediment control BMPs prior to discharge of runoff from a site. Drainage swales may be lined or unlined, but if an unlined swale is used, it must be well compacted and capable of resisting erosive velocities.

Appropriate Uses

Earth dikes and drainage swales are typically used to control the flow path of runoff at a construction site by diverting runoff around areas prone to erosion, such as steep slopes. Earth dikes and drainage swales may also be constructed as temporary conveyance features. This will direct runoff to additional sediment control treatment BMPs, such as sediment traps or basins.

Design and Installation

When earth dikes are used to divert water for slope protection, the earth dike typically consists of a horizontal ridge of soil placed perpendicular to the slope and angled slightly to provide drainage along the contour. The dike is used in conjunction with a swale or a small channel upslope of the berm to convey the diverted water. Temporary diversion dikes can be constructed by excavation of a V-shaped trench or ditch and placement of the fill on the downslope side of the cut. There are two types of placement for temporary slope diversion dikes:

- A dike located at the top of a slope to divert upland runoff away from the disturbed area and convey it in a temporary or permanent channel.
- A diversion dike located at the base or mid-slope of a disturbed area to intercept runoff and reduce the effective slope length.

Depending on the project, either an earth dike or drainage swale may be more appropriate. If there is a need for cut on the project, then an excavated drainage swale may be better suited. When the project is primarily fill, then a conveyance constructed using a berm may be the better option.

Earth Dikes and Drainage Swales	
Functions	
Erosion Control	Yes
Sediment Control	Moderate
Site/Material Management	No

All dikes or swales receiving runoff from a disturbed area should direct stormwater to a sediment control BMP such as a sediment trap or basin.

November 2010 Urban Drainage and Flood Control District ED/DS-1
Urban Storm Drainage Criteria Manual Volume 3



Photograph ED/DS-1. Example of an earth dike used to divert flows at a construction site. Photo courtesy of CDOT.

EC-10 Earth Dikes and Drainage Swales (ED/DS)

Unlined dikes or swales should only be used for intercepting sheet flow runoff and are not intended for diversion of concentrated flows.

Details with notes are provided for several design variations, including:

ED-1. Unlined Earth Dike formed by Berm

DS-1. Unlined Excavated Swale

DS-3. ECB-lined Swale

DS-4. Synthetic-lined Swale

DS-5. Riprap-lined Swale

The details also include guidance on permissible velocities for cohesive channels if unlined approaches will be used.


Maintenance and Removal

Inspect earth dikes for stability, compaction, and signs of erosion and repair. Inspect side slopes for erosion and damage to erosion control fabric. Stabilize slopes and repair fabric as necessary. If there is reoccurring extensive damage, consider installing rock check dams or lining the channel with riprap.

If drainage swales are not permanent, remove dikes and fill channels when the upstream area is stabilized. Stabilize the fill or disturbed area immediately following removal by revegetation or other permanent stabilization method approved by the local jurisdiction.

ED/DS-2 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Earth Dikes and Drainage Swales (ED/DS) EC-10



November 2010 Urban Drainage and Flood Control District ED/DS-3
Urban Storm Drainage Criteria Manual Volume 3

Earth Dikes and Drainage Swales (ED/DS) EC-10

EARTH DIKE AND DRAINAGE SWALE MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - SWALES SHALL REMAIN IN PLACE UNTIL THE END OF CONSTRUCTION; IF APPROVED BY LOCAL JURISDICTION, SWALES MAY BE LEFT IN PLACE.
 - WHEN A SWALE IS REMOVED, THE DISTURBED AREA SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED IN A MANNER APPROVED BY LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF COLORADO SPRINGS, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

November 2010 Urban Drainage and Flood Control District ED/DS-5
Urban Storm Drainage Criteria Manual Volume 3

Concrete Washout Area (CWA) MM-1

Description

Concrete waste management involves designating and properly managing a specific area of the construction site as a concrete washout area. A concrete washout area can be created using one of several approaches designed to receive wash water from washing of tools and concrete mixer chutes, liquid concrete waste from dump trucks, mobile batch mixers, or pump trucks. Three basic approaches are available: excavation of a pit in the ground, use of an above ground storage area, or use of prefabricated haul-away concrete washout containers. Surface discharges of concrete washout water from construction sites are prohibited.



Photograph CWA-1. Example of concrete washout area. Note gravel tracking pad for access and sign.

Appropriate Uses

Concrete washout areas must be designated on all sites that will generate concrete wash water or liquid concrete waste from onsite concrete mixing or concrete delivery.

Because pH is a pollutant of concern for washout activities, when unlined pits are used for concrete washout, the soil must have adequate buffering capacity to result in protection of state groundwater standards; otherwise, a liner/containment must be used. The following management practices are recommended to prevent an impact from unlined pits to groundwater:

- The use of the washout site should be temporary (less than 1 year), and
- The washout site should not be located in an area where shallow groundwater may be present, such as near natural drainages, springs, or wetlands.

Design and Installation

Concrete washout activities must be conducted in a manner that does not contribute pollutants to surface waters or stormwater runoff. Concrete washout areas may be lined or unlined excavated pits in the ground, commercially manufactured prefabricated washout containers, or aboveground holding areas constructed of berms, sandbags or straw bales with a plastic liner.

Although unlined washout areas may be used, lined pits may be required to protect groundwater under certain conditions.

Do not locate an unlined washout area within 400 feet of any natural drainage pathway or waterbody or within 1,000 feet of any wells or drinking water sources. Even for lined concrete washouts, it is advisable to locate the facility away from waterbodies and drainage paths. If site constraints make these

Concrete Washout Area	
Functions	
Erosion Control	No
Sediment Control	No
Site/Material Management	Yes

November 2010 Urban Drainage and Flood Control District CWA-1
Urban Storm Drainage Criteria Manual Volume 3

MM-1 Concrete Washout Area (CWA)

setbacks infeasible or if highly permeable soils exist in the area, then the pit must be installed with an impermeable liner (16 mil minimum thickness) or surface storage alternatives using prefabricated concrete washout devices or a lined aboveground storage area should be used.

Design details with notes are provided in Detail CWA-1 for pits and CWA-2 for aboveground storage areas. Pre-fabricated concrete washout container information can be obtained from vendors.

Maintenance and Removal

A key consideration for concrete washout areas is to ensure that adequate signage is in place identifying the location of the washout area. Part of inspecting and maintaining washout areas is ensuring that adequate signage is provided and in good repair and that the washout area is being used, as opposed to washout in non-designated areas of the site.

Remove concrete waste in the washout area, as needed to maintain BMP function (typically when filled to about two-thirds of its capacity). Collect concrete waste and deliver offsite to a designated disposal location.

Upon termination of use of the washout site, accumulated solid waste, including concrete waste and any contaminated soils, must be removed from the site to prevent on-site disposal of solid waste. If the wash water is allowed to evaporate and the concrete hardens, it may be recycled.




Photograph CWA-2. Prefabricated concrete washout. Photo courtesy of CDOT.



Photograph CWA-3. Earthen concrete washout. Photo courtesy of CDOT.

CWA-2 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Concrete Washout Area (CWA) MM-1



CWA-1. CONCRETE WASHOUT AREA

CWA INSTALLATION NOTES

- SEE PLAN VIEW FOR: -CWA INSTALLATION LOCATION.
- DO NOT LOCATE AN UNLINED CWA WITHIN 400' OF ANY NATURAL DRAINAGE PATHWAY OR WATERBODY. DO NOT LOCATE WITHIN 1,000' OF ANY WELLS OR DRINKING WATER SOURCES. IF SITE CONSTRAINTS MAKE THIS INFEASIBLE, OR IF HIGHLY PERMEABLE SOILS EXIST ON SITE, THE CWA MUST BE INSTALLED WITH AN IMPERMEABLE LINER (16 MIL MIN. THICKNESS) OR SURFACE STORAGE ALTERNATIVES USING PREFABRICATED CONCRETE WASHOUT DEVICES OR A LINED ABOVE GROUND STORAGE ARE SHOULD BE USED.
- THE CWA SHALL BE INSTALLED PRIOR TO CONCRETE PLACEMENT ON SITE.
- CWA SHALL INCLUDE A FLAT SUBSURFACE PIT THAT IS AT LEAST 8' BY 8' SLOPES LEADING OUT OF THE SUBSURFACE PIT SHALL BE 3:1 OR FLATTER. THE PIT SHALL BE AT LEAST 3' DEEP.
- BERM SURROUNDING SIDES AND BACK OF THE CWA SHALL HAVE MINIMUM HEIGHT OF 1'.
- VEHICLE TRACKING PAD SHALL BE SLOPED 2% TOWARDS THE CWA.
- SIGNS SHALL BE PLACED AT THE CONSTRUCTION ENTRANCE, AT THE CWA, AND ELSEWHERE AS NECESSARY TO CLEARLY INDICATE THE LOCATION OF THE CWA TO OPERATORS OF CONCRETE TRUCKS AND PUMP RIGS.
- USE EXCAVATED MATERIAL FOR PERIMETER BERM CONSTRUCTION.

November 2010 Urban Drainage and Flood Control District CWA-3
Urban Storm Drainage Criteria Manual Volume 3

MM-1 Concrete Washout Area (CWA)

CWA MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - THE CWA SHALL BE REPAIRED, CLEANED, OR ENLARGED AS NECESSARY TO MAINTAIN CAPACITY FOR CONCRETE WASTE. CONCRETE MATERIALS, ACCUMULATED IN PIT, SHALL BE REMOVED ONCE THE MATERIALS HAVE REACHED A DEPTH OF 2'.
 - CONCRETE WASHOUT WATER, WASTED PIECES OF CONCRETE AND ALL OTHER DEBRIS IN THE SUBSURFACE PIT SHALL BE TRANSPORTED FROM THE JOB SITE IN A WATER-TIGHT CONTAINER AND DISPOSED OF PROPERLY.
 - THE CWA SHALL REMAIN IN PLACE UNTIL ALL CONCRETE FOR THE PROJECT IS PLACED.
 - WHEN THE CWA IS REMOVED, COVER THE DISTURBED AREA WITH TOP SOIL, SEED AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY THE LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM DOUGLAS COUNTY, COLORADO AND THE CITY OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

CWA-4 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

REVISION
DATE
BY
INITIALS
DATE
BY
INITIALS

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext. 233

GESC DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC


PROJECT NO.
01-0355.001.02

DOC CON #
0021-GESC DTLS

SHEET
21 OF 28

Silt Fence (SF)

SC-1



November 2010 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 SF-3

SC-1

Silt Fence (SF)

SILT FENCE INSTALLATION NOTES

1. SILT FENCE MUST BE PLACED AWAY FROM THE TOE OF THE SLOPE TO ALLOW FOR WATER PONDING. SILT FENCE AT THE TOE OF A SLOPE SHOULD BE INSTALLED IN A FLAT LOCATION AT LEAST SEVERAL FEET (2-5 FT) FROM THE TOE OF THE SLOPE TO ALLOW ROOM FOR PONDING AND DEPOSITION.
2. A UNIFORM 6" X 4" ANCHOR TRENCH SHALL BE EXCAVATED USING TRENCHER OR SILT FENCE INSTALLATION DEVICE, NO ROAD GRADERS, BACKHOES, OR SIMILAR EQUIPMENT SHALL BE USED.
3. COMPACT ANCHOR TRENCH BY HAND WITH A "JUMPING JACK" OR BY WHEEL ROLLING. COMPACTATION SHALL BE SUCH THAT SILT FENCE RESISTS BEING PULLED OUT OF ANCHOR TRENCH BY HAND.
4. SILT FENCE SHALL BE PULLED TIGHT AS IT IS ANCHORED TO THE STAKES. THERE SHOULD BE NO NOTICEABLE SAG BETWEEN STAKES AFTER IT HAS BEEN ANCHORED TO THE STAKES.
5. SILT FENCE FABRIC SHALL BE ANCHORED TO THE STAKES USING 1" HEAVY DUTY STAPLES OR NAILS WITH 1" HEADS. STAPLES AND NAILS SHOULD BE PLACED 3" ALONG THE FABRIC DOWN THE STAKE.
6. AT THE END OF A RUN OF SILT FENCE ALONG A CONTOUR, THE SILT FENCE SHOULD BE TURNED PERPENDICULAR TO THE CONTOUR TO CREATE A "J-HOOK." THE "J-HOOK" EXTENDING PERPENDICULAR TO THE CONTOUR SHOULD BE OF SUFFICIENT LENGTH TO KEEP RUNOFF FROM FLOWING AROUND THE END OF THE SILT FENCE (TYPICALLY 10' - 20').
7. SILT FENCE SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.

SILT FENCE MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 4. SEDIMENT ACCUMULATED UPSTREAM OF THE SILT FENCE SHALL BE REMOVED AS NEEDED TO MAINTAIN THE FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 6".
 5. REPAIR OR REPLACE SILT FENCE WHEN THERE ARE SIGNS OF WEAR, SUCH AS SAGGING, TEARING, OR COLLAPSE.
 6. SILT FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION, OR IS REPLACED BY AN EQUIVALENT PERIMETER SEDIMENT CONTROL BMP.
 7. WHEN SILT FENCE IS REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- (DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

SF-4 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 November 2010

Rock Sock (RS)

SC-5

Description

A rock sock is constructed of gravel that has been wrapped by wire mesh or a geotextile to form an elongated cylindrical filter. Rock socks are typically used either as a perimeter control or as part of inlet protection. When placed at angles in the curb line, rock socks are typically referred to as curb socks. Rock socks are intended to trap sediment from stormwater runoff that flows onto roadways as a result of construction activities.



Photograph RS-1. Rock socks placed at regular intervals in a curb line can help reduce sediment loading to storm sewer inlets. Rock socks can also be used as perimeter controls.

Appropriate Uses

Rock socks can be used at the perimeter of a disturbed area to control localized sediment loading. A benefit of rock socks as opposed to other perimeter controls is that they do not have to be trenched or staked into the ground; therefore, they are often used on roadway construction projects where paved surfaces are present.

Use rock socks in inlet protection applications when the construction of a roadway is substantially complete and the roadway has been directly connected to a receiving storm system.

Design and Installation

When rock socks are used as perimeter controls, the maximum recommended tributary drainage area per 100 lineal feet of rock socks is approximately 0.25 acres with disturbed slope length of up to 150 feet and a tributary slope gradient no steeper than 3:1. A rock sock design detail and notes are provided in Detail RS-1. Also see the Inlet Protection Fact Sheet for design and installation guidance when rock socks are used for inlet protection and in the curb line.

When placed in the gutter adjacent to a curb, rock socks should protrude no more than two feet from the curb in order for traffic to pass safely. If located in a high traffic area, place construction markers to alert drivers and street maintenance workers of their presence.

Maintenance and Removal

Rock socks are susceptible to displacement and breaking due to vehicle traffic. Inspect rock socks for damage and repair or replace as necessary. Remove sediment by sweeping or vacuuming as needed to maintain the functionality of the BMP, typically when sediment has accumulated behind the rock sock to one-half of the sock's height.


Once upstream stabilization is complete, rock socks and accumulated sediment should be removed and properly disposed.

Rock Sock	
Functions	
Erosion Control	No
Sediment Control	Yes
Site/Material Management	No

November 2010 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 RS-1

SC-5

Rock Sock (RS)



RS-2 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 November 2010

Rock Sock (RS)

SC-5

ROCK SOCK MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. ROCK SOCKS SHALL BE REPLACED IF THEY BECOME HEAVILY SOILED, OR DAMAGED BEYOND REPAIR.
5. SEDIMENT ACCUMULATED UPSTREAM OF ROCK SOCKS SHALL BE REMOVED AS NEEDED TO MAINTAIN FUNCTIONALITY OF THE BMP, TYPICALLY WHEN DEPTH OF ACCUMULATED SEDIMENTS IS APPROXIMATELY 1/2 OF THE HEIGHT OF THE ROCK SOCK.
6. ROCK SOCKS ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
7. WHEN ROCK SOCKS ARE REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO AND CITY OF AURORA, COLORADO, NOT AVAILABLE IN AUTOCAD)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

NOTE: THE DETAILS INCLUDED WITH THIS FACT SHEET SHOW COMMONLY USED, CONVENTIONAL METHODS OF ROCK SOCK INSTALLATION IN THE DENVER METROPOLITAN AREA. THERE ARE MANY OTHER SIMILAR PROPRIETARY PRODUCTS ON THE MARKET. UDFCD NEITHER ENDORSES NOR DISCOURAGES USE OF PROPRIETARY PROTECTION PRODUCTS; HOWEVER, IN THE EVENT PROPRIETARY METHODS ARE USED, THE APPROPRIATE DETAIL FROM THE MANUFACTURER MUST BE INCLUDED IN THE SUMP AND THE BMP MUST BE INSTALLED AND MAINTAINED AS SHOWN IN THE MANUFACTURER'S DETAILS.

November 2010 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 RS-3

Sediment Basin (SB)

SC-7

Description

A sediment basin is a temporary pond built on a construction site to capture eroded or disturbed soil transported in storm runoff prior to discharge from the site. Sediment basins are designed to capture site runoff and slowly release it to allow time for settling of sediment prior to discharge. Sediment basins are often constructed in locations that will later be modified to serve as post-construction stormwater basins.



Photograph SB-1. Sediment basin at the toe of a slope. Photo courtesy of WVE.

Appropriate Uses

Most large construction sites (typically greater than 2 acres) will require one or more sediment basins for effective management of construction site runoff. On linear construction projects, sediment basins may be impractical; instead, sediment traps or other combinations of BMPs may be more appropriate.

Sediment basins should not be used as stand-alone sediment controls. Erosion and other sediment controls should also be implemented upstream.

When feasible, the sediment basin should be installed in the same location where a permanent post-construction detention pond will be located.

Design and Installation

The design procedure for a sediment basin includes these steps:

- **Basin Storage Volume:** Provide a storage volume of at least 3,600 cubic feet per acre of drainage area. To the extent practical, undisturbed and/or off-site areas should be diverted around sediment basins to prevent "clean" runoff from mixing with runoff from disturbed areas. For undisturbed areas (both on-site and off-site) that cannot be diverted around the sediment basin, provide a minimum of 500 ft³/acre of storage for undeveloped (but stable) off-site areas in addition to the 3,600 ft³/acre for disturbed areas. For stable, developed areas that cannot be diverted around the sediment basin, storage volume requirements are summarized in Table SB-1.
- **Basin Geometry:** Design basin with a minimum length-to-width ratio of 2:1 (L:W). If this cannot be achieved because of site space constraints, baffling may be required to extend the effective distance between the inflow point(s) and the outlet to minimize short-circuiting.
- **Dam Embankment:** It is recommended that embankment slopes be 4:1 (H:V) or flatter and no steeper than 3:1 (H:V) in any location.

Sediment Basins	
Functions	
Erosion Control	No
Sediment Control	Yes
Site/Material Management	No

August 2013 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 SB-1

SC-7

Sediment Basin (SB)

- **Inflow Structure:** For concentrated flow entering the basin, provide energy dissipation at the point of inflow.

Table SB-1. Additional Volume Requirements for Undisturbed and Developed Tributary Areas Draining through Sediment Basins

Imperviousness (%)	Additional Storage Volume (ft ³) Per Acre of Tributary Area
Undeveloped	500
10	800
20	1230
30	1600
40	2030
50	2470
60	2980
70	3560
80	4360
90	5300
100	6460

- **Outlet Works:** The outlet pipe shall extend through the embankment at a minimum slope of 0.5 percent. Outlet works can be designed using one of the following approaches:
 - **Riser Pipe (Simplified Detail):** Detail SB-1 provides a simplified design for basins treating no more than 15 acres.
 - **Orifice Plate or Riser Pipe:** Follow the design criteria for Full Spectrum Detention outlets in the EDB Fact Sheet provided in Chapter 4 of this manual for sizing of outlet perforations with an emptying time of approximately 72 hours. In lieu of the trash rack, pack uniformly sized 1½" - to 2-inch gravel in front of the plate or surrounding the riser pipe. This gravel will need to be cleaned out frequently during the construction period as sediment accumulates within it. The gravel pack will need to be removed and disposed of following construction to reclaim the basin for use as a permanent detention facility. If the basin will be used as a permanent extended detention basin for the site, a trash rack will need to be installed once contributing drainage areas have been stabilized and the gravel pack and accumulated sediment have been removed.
 - **Floating Skimmer:** If a floating skimmer is used, install it using manufacturer's recommendations. Illustration SB-1 provides an illustration of a Faircloth Skimmer Floating Outlet™, one of the more commonly used floating skimmer outlets. A skimmer should be designed to release the design volume in no less than 48 hours. The use of a floating skimmer outlet can increase the sediment capture efficiency of a basin significantly. A floating outlet continually decants cleanest water off the surface of the pond and releases cleaner water than would discharge from a perforated riser pipe or plate.

SB-2 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 August 2013

Sediment Basin (SB)

SC-7




Illustration SB-1. Outlet structure for a temporary sediment basin - Faircloth Skimmer Floating Outlet. Illustration courtesy of J. W. Faircloth & Sons, Inc., FairclothSkimmer.com.

- **Outlet Protection and Spillway:** Consider all flow paths for runoff leaving the basin, including protection at the typical point of discharge as well as overtopping.
 - **Outlet Protection:** Outlet protection should be provided where the velocity of flow will exceed the maximum permissible velocity of the material of the waterway into which discharge occurs. This may require the use of a riprap apron at the outlet location and/or other measures to keep the waterway from eroding.
 - **Emergency Spillway:** Provide a stabilized emergency overflow spillway for rainstorms that exceed the capacity of the sediment basin volume and its outlet. Protect basin embankments from erosion and overtopping. If the sediment basin will be converted to a permanent detention basin, design and construct the emergency spillway(s) as required for the permanent facility. If the sediment basin will not become a permanent detention basin, it may be possible to substitute a heavy poly-vinyl membrane or properly bedded rock cover to line the spillway and downstream embankment, depending on the height, slope, and width of the embankments.

August 2013 Urban Drainage and Flood Control District
Urban Storm Drainage Criteria Manual Volume 3 SB-3

127 S. DENVER AVE.
FT. LUTON, CO. 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc LLC

DATE: 06/25/21
BY: CFC
REVISION: INITIAL REUSE
CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602) 264-7263 ext. 233

GESC DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SHEET RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0023-GESC DTLs
SHEET
23 OF 28

SC-7 Sediment Basin (SB)


Maintenance and Removal

Maintenance activities include the following:

- Dredge sediment from the basin, as needed to maintain BMP effectiveness, typically when the design storage volume is no more than one-third filled with sediment.
- Inspect the sediment basin embankments for stability and seepage.
- Inspect the inlet and outlet of the basin, repair damage, and remove debris. Remove, clean and replace the gravel around the outlet on a regular basis to remove the accumulated sediment within it and keep the outlet functioning.
- Be aware that removal of a sediment basin may require dewatering and associated permit requirements.
- Do not remove a sediment basin until the upstream area has been stabilized with vegetation.

Final disposition of the sediment basin depends on whether the basin will be converted to a permanent post-construction stormwater basin or whether the basin area will be returned to grade. For basins being converted to permanent detention basins, remove accumulated sediment and reconfigure the basin and outlet to meet the requirements of the final design for the detention facility. If the sediment basin is not to be used as a permanent detention facility, fill the excavated area with soil and stabilize with vegetation.

Sediment Basin (SB) SC-7



SC-7 Sediment Basin (SB)

TABLE SB-1. SIZING INFORMATION FOR STANDARD SEDIMENT BASIN			
Upstream Drainage Area (rounded to nearest acre), (ac)	Basin Bottom Width (W), (ft)	Spillway Crest Length (CL), (ft)	Hole Diameter (HD), (in)
1	12 1/2	2	9/32
2	21	3	15/64
3	28	5	1/8
4	33 1/2	6	5/16
5	38 1/2	8	3/8
6	43	9	7/16
7	47 1/2	11	1/2
8	51	12	5/8
9	55	13	3/4
10	58 1/2	15	15/16
11	61	16	1
12	64	18	1 1/16
13	67 1/2	19	1 1/8
14	70 1/2	21	1 1/4
15	73 1/2	22	1 1/2

SEDIMENT BASIN INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION OF SEDIMENT BASIN.
 - TYPE OF BASIN (STANDARD BASIN OR NONSTANDARD BASIN).
 - FOR STANDARD BASIN, BOTTOM WIDTH W, CREST LENGTH CL, AND HOLE DIAMETER, HD.
 - FOR NONSTANDARD BASIN, SEE CONSTRUCTION DRAWINGS FOR DESIGN OF BASIN INCLUDING RISER HEIGHT H, NUMBER OF COLUMNS N, HOLE DIAMETER HD AND PIPE DIAMETER D.
- FOR STANDARD BASIN, BOTTOM DIMENSION MAY BE MODIFIED AS LONG AS BOTTOM AREA IS NOT REDUCED.
- SEDIMENT BASINS SHALL BE INSTALLED PRIOR TO ANY OTHER LAND-DISTURBING ACTIVITY THAT RELIES ON ON BASINS AS A STORMWATER CONTROL.
- EMBANKMENT MATERIAL SHALL CONSIST OF SOIL FREE OF DEBRIS, ORGANIC MATERIAL, AND ROCKS OR CONCRETE GREATER THAN 3 INCHES AND SHALL HAVE A MINIMUM OF 15 PERCENT BY WEIGHT PASSING THE NO. 200 SIEVE.
- EMBANKMENT MATERIAL SHALL BE COMPACTED TO AT LEAST 95 PERCENT OF MAXIMUM DENSITY IN ACCORDANCE WITH ASTM D698.
- PIPE SCH 40 OR GREATER SHALL BE USED.
- THE DETAILS SHOWN ON THESE SHEETS PERTAIN TO STANDARD SEDIMENT BASIN(S) FOR DRAINAGE AREAS LESS THAN 15 ACRES. SEE CONSTRUCTION DRAWINGS FOR EMBANKMENT, STORAGE VOLUME, SPILLWAY, OUTLET, AND OUTLET PROTECTION DETAILS FOR ANY SEDIMENT BASIN(S) THAT HAVE BEEN INDIVIDUALLY DESIGNED FOR DRAINAGE AREAS LARGER THAN 15 ACRES.

Sediment Basin (SB) SC-7

SEDIMENT BASIN MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
- FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
- WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
- SEDIMENT ACCUMULATED IN BASIN SHALL BE REMOVED AS NEEDED TO MAINTAIN BMP EFFECTIVENESS, TYPICALLY WHEN SEDIMENT DEPTH REACHES ONE FOOT (I.E., TWO FEET BELOW THE SPILLWAY CREST).
- SEDIMENT BASINS ARE TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND GRASS COVER IS ACCEPTED BY THE LOCAL JURISDICTION.
- WHEN SEDIMENT BASINS ARE REMOVED, ALL DISTURBED AREAS SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.

(DETAILS ADAPTED FROM DOUGLAS COUNTY, COLORADO)

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

Construction Fence (CF) SM-3

Description

A construction fence restricts site access to designated entrances and exits, delineates construction site boundaries, and keeps construction out of sensitive areas such as natural areas to be preserved as open space, wetlands and riparian areas.

Appropriate Uses

A construction fence can be used to delineate the site perimeter and locations within the site where access is restricted to protect natural resources such as wetlands, waterbodies, trees, and other natural areas of the site that should not be disturbed.

If natural resource protection is an objective, then the construction fencing should be used in combination with other perimeter control BMPs such as silt fence, sediment control logs or similar measures.

Design and Installation

Construction fencing may be chain link or plastic mesh and should be installed following manufacturer's recommendations. See Detail CF-1 for typical installations.


Do not place construction fencing in areas within work limits of machinery.

Maintenance and Removal

- Inspect fences for damage; repair or replace as necessary.
- Fencing should be tight and any areas with slumping or fallen posts should be reinstalled.
- Fencing should be removed once construction is complete.

Construction Fence	
Functions	
Erosion Control	No
Sediment Control	No
Site/Material Management	Yes

SM-3 Construction Fence (CF)



CONSTRUCTION FENCE INSTALLATION NOTES

- SEE PLAN VIEW FOR:
 - LOCATION OF CONSTRUCTION FENCE.
- CONSTRUCTION FENCE SHOWN SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.
- CONSTRUCTION FENCE SHALL BE COMPOSED OF ORANGE, CONTRACTOR-GRADE MATERIAL THAT IS AT LEAST 4' HIGH. METAL POSTS SHOULD HAVE A PLASTIC CAP FOR SAFETY.
- STUDDED STEEL TEE POSTS SHALL BE UTILIZED TO SUPPORT THE CONSTRUCTION FENCE. MAXIMUM SPACING FOR STEEL TEE POSTS SHALL BE 10'.
- CONSTRUCTION FENCE SHALL BE SECURELY FASTENED TO THE TOP, MIDDLE, AND BOTTOM OF EACH POST.

Construction Fence (CF) SM-3

CONSTRUCTION FENCE MAINTENANCE NOTES

- INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
 - FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
 - WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
 - CONSTRUCTION FENCE SHALL BE REPAIRED OR REPLACED WHEN THERE ARE SIGNS OF DAMAGE SUCH AS RIPS OR SAGS. CONSTRUCTION FENCE IS TO REMAIN IN PLACE UNTIL THE UPSTREAM DISTURBED AREA IS STABILIZED AND APPROVED BY THE LOCAL JURISDICTION.
 - WHEN CONSTRUCTION FENCES ARE REMOVED, ALL DISTURBED AREAS ASSOCIATED WITH THE INSTALLATION, MAINTENANCE, AND/OR REMOVAL OF THE FENCE SHALL BE COVERED WITH TOPSOIL, SEEDED AND MULCHED, OR OTHERWISE STABILIZED AS APPROVED BY LOCAL JURISDICTION.
- NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAIL ADAPTED FROM TOWN OF PARKER, COLORADO, NOT AVAILABLE IN AUTOCAD)

Vehicle Tracking Control (VTC) SM-4

Description

Vehicle tracking controls provide stabilized construction site access where vehicles exit the site onto paved public roads. An effective vehicle tracking control helps remove sediment (mud or dirt) from vehicles, reducing tracking onto the paved surface.

Appropriate Uses

Implement a stabilized construction entrance or vehicle tracking control where frequent heavy vehicle traffic exits the construction site onto a paved roadway. An effective vehicle tracking control is particularly important during the following conditions:

- Wet weather periods when mud is easily tracked off site.
- During dry weather periods where dust is a concern.
- When poorly drained, clayey soils are present on site.

Although wheel washes are not required in designs of vehicle tracking controls, they may be needed at particularly muddy sites.

Design and Installation

Construct the vehicle tracking control on a level surface. Where feasible, grade the tracking control towards the construction site to reduce off-site runoff. Place signage, as needed, to direct construction vehicles to the designated exit through the vehicle tracking control. There are several different types of stabilized construction entrances including:

VTC-1. Aggregate Vehicle Tracking Control. This is a coarse-aggregate surfaced pad underlain by a geotextile. This is the most common vehicle tracking control, and when properly maintained can be effective at removing sediment from vehicle tires.

VTC-2. Vehicle Tracking Control with Construction Mat or Turf Reinforcement Mat. This type of control may be appropriate for site access at very small construction sites with low traffic volume over vegetated areas. Although this application does not typically remove sediment from vehicles, it helps protect existing vegetation and provides a stabilized entrance.

Vehicle Tracking Control	
Functions	
Erosion Control	Moderate
Sediment Control	Yes
Site/Material Management	Yes

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
(720) 294-1330
FAX

Western Engineering Consultants, Inc LLC

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext. 233

GESC DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0024-GESC DTLS
SHEET
24 OF 28

SM-4 Vehicle Tracking Control (VTC)

VTC-3. **Stabilized Construction Entrance/Exit with Wheel Wash.** This is an aggregate pad, similar to VTC-1, but includes equipment for tire washing. The wheel wash equipment may be as simple as hand-held power washing equipment to more advance proprietary systems. When a wheel wash is provided, it is important to direct wash water to a sediment trap prior to discharge from the site.

Vehicle tracking controls are sometimes installed in combination with a sediment trap to treat runoff.

Maintenance and Removal

Inspect the area for degradation and replace aggregate or material used for a stabilized entrance/exit as needed. If the area becomes clogged and ponds water, remove and dispose of excess sediment or replace material with a fresh layer of aggregate as necessary.

With aggregate vehicle tracking controls, ensure rock and debris from this area do not enter the public right-of-way.

Remove sediment that is tracked onto the public right of way daily or more frequently as needed. Excess sediment in the roadway indicates that the stabilized construction entrance needs maintenance.

Ensure that drainage ditches at the entrance/exit area remain clear.

A stabilized entrance should be removed only when there is no longer the potential for vehicle tracking to occur. This is typically after the site has been stabilized.

When wheel wash equipment is used, be sure that the wash water is discharged to a sediment trap prior to discharge. Also inspect channels conveying the water from the wash area to the sediment trap and stabilize areas that may be eroding.


When a construction entrance/exit is removed, excess sediment from the aggregate should be removed and disposed of appropriately. The entrance should be promptly stabilized with a permanent surface following removal, typically by paving.



Photograph VTC-2. A vehicle tracking control pad with wheel wash facility. Photo courtesy of Tom Gore.

VTC-2 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Vehicle Tracking Control (VTC) SM-4



VTC-1. AGGREGATE VEHICLE TRACKING CONTROL

November 2010 Urban Drainage and Flood Control District VTC-3
Urban Storm Drainage Criteria Manual Volume 3

SM-4 Vehicle Tracking Control (VTC)

STABILIZED CONSTRUCTION ENTRANCE/EXIT INSTALLATION NOTES

1. SEE PLAN VIEW FOR
-LOCATION OF CONSTRUCTION ENTRANCE(S)/EXIT(S).
-TYPE OF CONSTRUCTION ENTRANCE(S)/EXIT(S) (WITH/WITHOUT WHEEL WASH, CONSTRUCTION MAT OR TRM).
2. CONSTRUCTION MAT OR TRM STABILIZED CONSTRUCTION ENTRANCES ARE ONLY TO BE USED ON SHORT DURATION PROJECTS (TYPICALLY RANGING FROM A WEEK TO A MONTH) WHERE THERE WILL BE LIMITED VEHICULAR ACCESS.
3. A STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL BE LOCATED AT ALL ACCESS POINTS WHERE VEHICLES ACCESS THE CONSTRUCTION SITE FROM PAVED RIGHT-OF-WAYS.
4. STABILIZED CONSTRUCTION ENTRANCE/EXIT SHALL BE INSTALLED PRIOR TO ANY LAND DISTURBING ACTIVITIES.
5. A NON-WOVEN GEOTEXTILE FABRIC SHALL BE PLACED UNDER THE STABILIZED CONSTRUCTION ENTRANCE/EXIT PRIOR TO THE PLACEMENT OF ROCK.
6. UNLESS OTHERWISE SPECIFIED BY LOCAL JURISDICTION, ROCK SHALL CONSIST OF DOT SECT. #703, AASHTO #3 COARSE AGGREGATE OR 6" (MINUS) ROCK.

STABILIZED CONSTRUCTION ENTRANCE/EXIT MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. ROCK SHALL BE REAPPLIED OR REGRADED AS NECESSARY TO THE STABILIZED ENTRANCE/EXIT TO MAINTAIN A CONSISTENT DEPTH.
5. SEDIMENT TRACKED ONTO PAVED ROADS IS TO BE REMOVED THROUGHOUT THE DAY AND AT THE END OF THE DAY BY SHOVELING OR SWEEPING. SEDIMENT MAY NOT BE WASHED DOWN STORM SEWER DRAINS.

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAILS ADAPTED FROM CITY OF BROOMFIELD, COLORADO, NOT AVAILABLE IN AUTOCAD)

VTC-6 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Stabilized Staging Area (SSA) SM-6

Description

A stabilized staging area is a clearly designated area where construction equipment and vehicles, stockpiles, waste bins, and other construction-related materials are stored. The contractor office trailer may also be located in this area. Depending on the size of the construction site, more than one staging area may be necessary.

Appropriate Uses

Most construction sites will require a staging area, which should be clearly designated in SWMP drawings. The layout of the staging area may vary depending on the type of construction activity. Staging areas located in roadways due to space constraints require special measures to avoid materials being washed into storm inlets.



Photograph SSA-1. Example of a staging area with a gravel surface to prevent mud tracking and reduce runoff. Photo courtesy of Douglas County.

Design and Installation

Stabilized staging areas should be completed prior to other construction activities beginning on the site. Major components of a stabilized staging area include:

- Appropriate space to contain storage and provide for loading/unloading operations, as well as parking if necessary.
- A stabilized surface, either paved or covered, with 3-inch diameter aggregate or larger.
- Perimeter controls such as silt fence, sediment control logs, or other measures.
- Construction fencing to prevent unauthorized access to construction materials.
- Provisions for Good Housekeeping practices related to materials storage and disposal, as described in the Good Housekeeping BMP Fact Sheet.
- A stabilized construction entrance/exit, as described in the Vehicle Tracking Control BMP Fact Sheet, to accommodate traffic associated with material delivery and waste disposal vehicles.

Over-sizing the stabilized staging area may result in disturbance of existing vegetation in excess of that required for the project. This increases costs, as well as requirements for long-term stabilization following the construction period. When designing the stabilized staging area, minimize the area of disturbance to the extent practical.

Stabilized Staging Area	
Functions	
Erosion Control	Yes
Sediment Control	Moderate
Site/Material	Yes

November 2010 Urban Drainage and Flood Control District SSA-1
Urban Storm Drainage Criteria Manual Volume 3

SM-6 Stabilized Staging Area (SSA)

Minimizing Long-Term Stabilization Requirements

- Utilize off-site parking and restrict vehicle access to the site.
- Use construction mats in lieu of rock when staging is provided in an area that will not be disturbed otherwise.
- Consider use of a bermed contained area for materials and equipment that do not require a stabilized surface.
- Consider phasing of staging areas to avoid disturbance in an area that will not be otherwise disturbed.

See Detail SSA-1 for a typical stabilized staging area and SSA-2 for a stabilized staging area when materials staging in roadways is required.


Maintenance and Removal

Maintenance of stabilized staging areas includes maintaining a stable surface cover of gravel, repairing perimeter controls, and following good housekeeping practices.

When construction is complete, debris, unused stockpiles and materials should be recycled or properly disposed. In some cases, this will require disposal of contaminated soil from equipment leaks in an appropriate landfill. Staging areas should then be permanently stabilized with vegetation or other surface cover planned for the development.

SSA-2 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Stabilized Staging Area (SSA) SM-6



SSA-1. STABILIZED STAGING AREA

STABILIZED STAGING AREA INSTALLATION NOTES

1. SEE PLAN VIEW FOR
-LOCATION OF STAGING AREA(S).
-CONTRACTOR MAY ADJUST LOCATION AND SIZE OF STAGING AREA WITH APPROVAL FROM THE LOCAL JURISDICTION.
2. STABILIZED STAGING AREA SHOULD BE APPROPRIATE FOR THE NEEDS OF THE SITE. OVERSIZING RESULTS IN A LARGER AREA TO STABILIZE FOLLOWING CONSTRUCTION.
3. STAGING AREA SHALL BE STABILIZED PRIOR TO OTHER OPERATIONS ON THE SITE.
4. THE STABILIZED STAGING AREA SHALL CONSIST OF A MINIMUM 3" THICK GRANULAR MATERIAL.
5. UNLESS OTHERWISE SPECIFIED BY LOCAL JURISDICTION, ROCK SHALL CONSIST OF DOT SECT. #703, AASHTO #3 COARSE AGGREGATE OR 6" (MINUS) ROCK.
6. ADDITIONAL PERIMETER BMPs MAY BE REQUIRED INCLUDING BUT NOT LIMITED TO SILT FENCE AND CONSTRUCTION FENCING.

STABILIZED STAGING AREA MAINTENANCE NOTES

1. INSPECT BMPs EACH WORKDAY, AND MAINTAIN THEM IN EFFECTIVE OPERATING CONDITION. MAINTENANCE OF BMPs SHOULD BE PROACTIVE, NOT REACTIVE. INSPECT BMPs AS SOON AS POSSIBLE (AND ALWAYS WITHIN 24 HOURS) FOLLOWING A STORM THAT CAUSES SURFACE EROSION, AND PERFORM NECESSARY MAINTENANCE.
2. FREQUENT OBSERVATIONS AND MAINTENANCE ARE NECESSARY TO MAINTAIN BMPs IN EFFECTIVE OPERATING CONDITION. INSPECTIONS AND CORRECTIVE MEASURES SHOULD BE DOCUMENTED THOROUGHLY.
3. WHERE BMPs HAVE FAILED, REPAIR OR REPLACEMENT SHOULD BE INITIATED UPON DISCOVERY OF THE FAILURE.
4. ROCK SHALL BE REAPPLIED OR REGRADED AS NECESSARY IF RUTTING OCCURS OR UNDERLYING SUBGRADE BECOMES EXPOSED.

November 2010 Urban Drainage and Flood Control District SSA-3
Urban Storm Drainage Criteria Manual Volume 3

SM-6 Stabilized Staging Area (SSA)

STABILIZED STAGING AREA MAINTENANCE NOTES

5. STABILIZED STAGING AREA SHALL BE ENLARGED IF NECESSARY TO CONTAIN PARKING, STORAGE, AND UNLOADING/LOADING OPERATIONS.
6. THE STABILIZED STAGING AREA SHALL BE REMOVED AT THE END OF CONSTRUCTION. THE GRANULAR MATERIAL SHALL BE REMOVED OR, IF APPROVED BY THE LOCAL JURISDICTION, USED ON SITE, AND THE AREA COVERED WITH TOPSOIL, SEED, AND MULCH OR OTHERWISE STABILIZED IN A MANNER APPROVED BY LOCAL JURISDICTION.

NOTE: MANY MUNICIPALITIES PROHIBIT THE USE OF RECYCLED CONCRETE AS GRANULAR MATERIAL FOR STABILIZED STAGING AREAS DUE TO DIFFICULTIES WITH RE-ESTABLISHMENT OF VEGETATION IN AREAS WHERE RECYCLED CONCRETE WAS PLACED.

NOTE: MANY JURISDICTIONS HAVE BMP DETAILS THAT VARY FROM UDFCD STANDARD DETAILS. CONSULT WITH LOCAL JURISDICTIONS AS TO WHICH DETAIL SHOULD BE USED WHEN DIFFERENCES ARE NOTED.

(DETAILS ADAPTED FROM DOUGLAS COUNTY, COLORADO, NOT AVAILABLE IN AUTOCAD)

SSA-4 Urban Drainage and Flood Control District November 2010
Urban Storm Drainage Criteria Manual Volume 3

Street Sweeping and Vacuuming (SS) SM-7

Description

Street sweeping and vacuuming remove sediment that has been tracked onto roadways to reduce sediment transport into storm drain systems or a surface waterway.

Appropriate Uses

Use this practice at construction sites where vehicles may track sediment offsite onto paved roadways.

Design and Installation

Street sweeping or vacuuming should be conducted when there is noticeable sediment accumulation on roadways adjacent to the construction site. Typically, this will be concentrated at the entrance/exit to the construction site. Well-maintained stabilized construction entrances, vehicle tracking controls and tire wash facilities can help reduce the necessary frequency of street sweeping and vacuuming.

On smaller construction sites, street sweeping can be conducted manually using a shovel and broom. Never wash accumulated sediment on roadways into storm drains.

Maintenance and Removal

- Inspect paved roads around the perimeter of the construction site on a daily basis and more frequently, as needed. Remove accumulated sediment, as needed.
- Following street sweeping, check inlet protection that may have been displaced during street sweeping.
- Inspect area to be swept for materials that may be hazardous prior to beginning sweeping operations.



Photograph SS-1. A street sweeper removes sediment and potential pollutants along the curb line at a construction site. Photo courtesy of Tom Gore.

Street Sweeping/ Vacuuming	
Functions	
Erosion Control	No
Sediment Control	Yes
Site/Material Management	Yes

November 2010 Urban Drainage and Flood Control District SS-1
Urban Storm Drainage Criteria Manual Volume 3

127 S. DENVER AVE.
FT. LUTPON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc. LLC

DATE BY
06/25/21 CFC

REVISION
INITIAL RELEASE

NO. 0


CONTACT: BRIAN SILVESTER
6950 W. MORELOS PL.
CHANDLER, AZ 85226
(602)264-7263 ext. 233

GESC DETAILS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
SAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0025-GESC DTLs
SHEET
25 OF 28



LANDSCAPE PLAN

SCALE: 1" = 30'

Native Lawn Mix
(90%) Buffalograss
(10%) Blue Grama
Seed @ 2-3 lb / 1000 sf

ALL SEED MIXES AS SPECIFIED BY PAWNEE BUTTES SEED COMPANY

SEED MAINTENANCE: MOW NATIVE LAWN MIX ABOUT 1/2 THE AMOUNT AS SODDED TURFGRASS OR AS NEEDED. HAND PULL WEED OR SPOT WEED USING A BROADLEAF APPLICATION DURING FIRST 3 GROWING SEASONS.

DISTURBED AREAS TO BE RESEEDDED WITH NATIVE LAWN MIX UNLESS OTHERWISE NOTED. RE: CIVIL PLANS

PLANT SCHEDULE

				QTY FOR REFERENCE ONLY. VERIFY ALL COUNTS PER PLAN	
TREES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	GAL
	CS	3	CATALPA SPECIOSA / NORTHERN CATALPA	B & B	2" CAL
	CO	3	CELTIS OCCIDENTALIS / COMMON HACKBERRY	B & B	2" CAL
	GTS	1	GLEDITSIA TRIACANTHOS INERMIS 'SHADEMASTER' TM / SHADEMASTER LOCUST	B & B	2" CAL
	JSG	5	JUNIPERUS SCOPULORUM 'MOONGLOW' / MOONGLOW JUNIPER	5' HT	
	QM	2	QUERCUS MUEHLENBERGII / CHINKAPIN OAK	B & B	2" CAL
SHRUBS	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	FIELD2
	AC	6	ARCTOSTAPHYLOS X COLORADOENSIS 'CHIEFTAIN' / MANZANITA	5 GAL	
	AI	9	ARONIA MELANOCARPA 'IROQUOIS BEAUTY' TM / BLACK CHOKEBERRY	5 GAL	
	RRF	3	FRANGULA ALNUS 'FINE LINE' / FINE LINE BUCHTHORN	5 GAL	
	PALS	36	PEROVSKIA ATRIPLICIFOLIA 'LITTLE SPIRE' / DWARF RUSSIAN SAGE	5 GAL	
	POD	6	PHYSOCARPUS OPULIFOLIUS 'DIABLO' / DIABLO NINEBARK	5 GAL	
	POL	15	PHYSOCARPUS OPULIFOLIUS 'LITTLE DEVIL' / DWARF PURPLE NINEBARK	5 GAL	
	Pw	13	PINUS MUGO 'WHITE BUD' / WHITE BUD MUGO PINE	5 GAL	
	PF	35	POTENTILLA FRUTICOSA 'GOLD DROP' / GOLDFINGER POTENTILLA	5 GAL	
	PBP	4	PRUNUS BESSEYI 'PAWNEE BUTTES' / SAND CHERRY	5 GAL	
GRASSES	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	
	BB	37	BOUTELOUA GRACILIS 'BLONDE AMBITION' / BLUE GRAMA	1 GAL	
	PVD	21	PANICUM VIRGATUM 'DALLAS BLUES' / DALLAS BLUES SWITCH GRASS	1 GAL	
	PVS	13	PANICUM VIRGATUM 'SHENENDOAH' / BURGUNDY SWITCH GRASS	1 GAL	
	SW	13	SPOROBOLUS WRIGHTII / BIG SACATON	1 GAL	
PERENNIALS	CODE	QTY	BOTANICAL / COMMON NAME	SIZE	
	EM	14	ECHINACEA PURPUREA 'MAGNUS' / MAGNUS PURPLE CONEFLOWER	1 GAL	
	LG	6	LAVANDULA X INTERMEDIA 'PROVENCE' / PROVENCE LAVENDER	1 GAL	
	PPP	30	PENSTEMON PINIFOLIUS / THREADLEAF BEARDTONGUE	4" POT	
GROUND COVERS	CODE	QTY	BOTANICAL / COMMON NAME	CONT	
	NLS	10,381 SF	NATIVE LAWN SEED MIX / PAWNEE BUTTES SEED CO NATIVE LAWN MIX 2-3 LBS PER 1000 SQUARE FEET.	SEED	
	TURF	3,497 SF	TURF / TEXAS HYBRID BLUEGRASS KENTUCKY BLUE GRASS BLEND TO MATCH EXISTING. SETBACK AND PARKWAY AREAS TO BE ON OVERALL DEVELOPMENT SYSTEM.	SOD	
MULCHES	CODE	QTY	BOTANICAL / COMMON NAME	CONT	
	RM	5,084 SF	ROCK MULCH / RIVER ROCK 1"-2" PER OWNER APPROVAL. PLACE TO A UNIFORM DEPTH OF 3" OVER PERMEABLE WEED BARRIER FABRIC.	MULCH	

REFERENCE NOTES SCHEDULE

SYMBOL	DESCRIPTION
	PLACE SHREDDDED CEDAR MULCH AROUND BASE OF ALL PERENNIALS AND GRASSES IN LARGE COBBLE AREAS. MASSED PERENNIALS TO RECEIVE LARGE RING AROUND ENTIRE GROUP (TYP). WOOD MULCH NOT REQUIRED AROUND BASE OF PLANTS LOCATED IN PEA GRAVEL.
	MINIMUM 3' ROOTBALL OFFSET FROM BUILDING, TYP.
	SEED ALL DISTURBED AREAS WITH NATIVE LAWN MIX UNLESS OTHERWISE NOTED.
	32 LANDSCAPE IMPROVEMENTS
	DESCRIPTION 14 G ROLL TOP STEEL EDGING, STAKED 30" OC MAX.
	SM-101 DESCRIPTION ALL SEEDED AREAS TO BE AMENDED AND HYDROSEEDDED. PLACE EROSION CONTROL MAT ON ALL SLOPES EXCEEDING 4:1.

HIGH PLAINS BANK
KEENESBURG, CO

FINAL LANDSCAPE PLAN

REVISIONS:

NO.	DATE	BY	DESCRIPTION
1	06/25/21	CFC	INITIAL RELEASE



LANDSCAPE PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO


Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

PROJ. No.:
DATE: 05.31.21
SCALE: See Sheet
DRAWN: JRO
CHKD BY: NAM
SHEET L10

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0026-LAND
SHEET
26 OF 28

127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330



GENERAL NOTES


- (Note: All references to "Contractor" are specific to "Landscape Contractor" unless notified as "General or other type of Contractor")
- CONTRACTOR IS RESPONSIBLE FOR VERIFYING QUANTITIES OF MATERIALS NEEDED TO COMPLETE THIS PLAN IN THE FIELD. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES BETWEEN THE DRAWINGS AND CONDITIONS IN THE FIELD. SUBSTITUTIONS OF PLANT MATERIAL ARE NOT ALLOWED WITHOUT APPROVAL FROM LANDSCAPE ARCHITECT GIVEN PRIOR TO INSTALLATION. GRAPHIC QTY'S. PREVAIL OVER WRITTEN QTY'S. PRIOR TO COMMENCEMENT OF WORK THE LANDSCAPE CONTRACTOR SHALL CONTACT OWNERS REPRESENTATIVE FOR SPECIFIC INSTRUCTIONS RELEVANT TO THE SEQUENCING AND SCOPE OF WORK.
 - CONTRACTOR IS RESPONSIBLE FOR INSTALLING ALL LANDSCAPE SHOWN ON THIS PLAN. ANY DEFICIENCIES OR DEVIATIONS FROM THIS PLAN ARE TO BE APPROVED BY OWNERS REPRESENTATIVE OR LANDSCAPE ARCHITECT. ANY CHANGES FROM THE APPROVED PLANS MAY REQUIRE APPROVAL FROM THE CITY OR COUNTY PLANNING DEPARTMENTS. LANDSCAPE CONTRACTOR TO PROVIDE ALL LABOR AND MATERIALS NECESSARY TO FURNISH SCOPE OF WORK AS SHOWN PER PLAN.
 - EXISTING TOPSOIL IS TO BE STOCKPILED AND USED TO ESTABLISH FINAL GRADES WITHIN LANDSCAPE AREAS. ALL STOCKPILED SOIL MUST BE CLEAR OF WEEDS, ROCKS AND DEBRIS BEFORE REUSE. ALL BERMED PLANTING BEDS TO BE CREATED WITH IMPORTED TOPSOIL.
 - GENERAL CONTRACTOR TO RE-SPREAD STOCKPILED SOIL AND ESTABLISH ROUGH GRADE CONDITIONS TO THE FOLLOWING SPECIFICATIONS:
 - A. 1" BELOW CURB FOR ALL SEEDED AREAS.
 - B. 2.5" BELOW CURB FOR ALL SODDED AREAS.
 - C. 4" BELOW CURB FOR ALL PLANTING, ROCK AND MULCH BEDS.
 - CONTRACTOR TO TILL PARKING LOT ISLANDS TO A DEPTH OF 30".
 - AMEND ALL PLANTING BEDS WITH CLASS 1 COMPOST. APPLY AT RATE OF 3 CYDS. PER 1000 SQUARE FEET TO ALL PLANTING BEDS AND MANICURED LAWN AREAS, AND 2 CYDS. PER 1000 SQUARE FEET FOR SEEDED AREAS. TILL, MIXING THOROUGHLY, INTO THE UPPER 8" OF SOIL.
 - FINE GRADE TO BE ESTABLISHED BY LANDSCAPE CONTRACTOR. FINE GRADE SHALL BE FREE OF ROCKS AND DEBRIS. FINE GRADE IN SEED AREAS SHALL BE FREE FROM ROCKS AND DEBRIS 1/2" AND GREATER. FINE GRADE IN SODDED AREAS SHALL BE FREE FROM ROCKS AND DEBRIS 1/2" AND GREATER. CONTRACTOR TO REPORT ANY POOR DRAINAGE CONDITIONS PRIOR TO CONSTRUCTION.
 - CONTRACTOR IS TO PROVIDE VERIFICATION THAT ALL SOD AND SEED IS OF THE SPECIES SHOWN ON THIS PLAN. NO SUBSTITUTIONS WILL BE ALLOWED. SOD TO BE LAID WITH TIGHT STAGGERED EDGES AND BE ROLLED AFTER INSTALLATION. SEEDED AREAS CANNOT BE SUBSTITUTED WITH SOD.
 - MULCHES: ALL PLANTING BEDS THAT CALL FOR WOOD MULCH TO RECEIVE 4" ORGANIC SHREDDED BARK MULCH. SHREDDED MULCH IS TO BE OF FIBROUS MATERIAL, NOT CHIPS OR CHUNKS. NO FABRIC IS TO BE PLACED UNDER WOOD/ORGANIC MULCH. ALL MULCHED BEDS ARE TO BE SPRAYED WITH WATER AFTER INSTALLATION TO HELP MULCH TO MAT DOWN.

ALL AREAS THAT CALL FOR COBBLE/ROCK MULCH TO RECEIVE MIN. 3" DEPTH, UNLESS NOTED OTHERWISE. USE PERMEABLE FABRIC UNDERLAYMENT FOR ALL COBBLE/AGGREGATE AREAS WITH SLOPES 3:1 AND LESS. USE QUICK RELEASE ORGANIC PRE-EMERGENT HERBICIDE FOR


ALL MULCHED AND PERENNIAL/PLANTING BEDS (AND FOR COBBLE/AGGREGATE AREAS WITH SLOPES EXCEEDING 3:1 GRADE. TREES IN COBBLE/ROCK MULCH, SOD AND SEEDED AREAS TO RECEIVE 4" DIAMETER OF WOOD MULCH RING. 3" DEEP. SHRUBS AND GROUNDCOVERS IN COBBLE/ROCK MULCH SOD AND SEEDED AREAS TO RECEIVE A WOOD MULCH RING AT 2X DIAMETER OF ROOT BALL. 3" DEPTH. NO FABRIC UNDERLAYMENT IN WOOD MULCH RINGS.

NOTES:


- DO NOT REMOVE OR CUT LEADER.
- PRUNE ONLY DEAD OR BROKEN BRANCHES IMMEDIATELY PRIOR TO PLANTING.
- DO NOT REMOVE ANY DOUBLE LEADER, UNLESS OTHERWISE DIRECTED BY OWNERS REPRESENTATIVE.
- KEEP PLANTS MOIST AND SHADED UNTIL PLANTING.
- AMENDED BACKFILL SHALL BE AS STATED ON THIS SHEET.
- MARK THE NORTH SIDE OF TREE IN THE NURSERY, AND ROTATE TREE TO FACE NORTH AT THE SITE WHENEVER POSSIBLE.
- PINE AND SPRUCE TREES TO BE SPRAYED FOR IPS BARK BEETLE PRIOR TO PLANTING. COORDINATE WITH CITY FORESTRY FOR CURRENT INSECT AND DISEASE RECOMMENDATIONS PRIOR TO PLANTING.
- ALL TREES TO BE DEEP WATERED AT TIME OF PLANTING.




EVERGREEN TREE PLANTING DETAIL



DECIDUOUS TREE PLANTING DETAIL



SHRUB PLANTING DETAIL



FABRIC CUTOUT / WOOD MULCH RING DETAIL

- CONTRACTOR IS TO PROVIDE A ONE YEAR WARRANTY ON ALL PLANT MATERIAL, TURF, IRRIGATION COMPONENTS, AND WORKMANSHIP. REPLACEMENT PLANT MATERIALS SHALL BE OF THE SAME SPECIES AND SIZE AS THE DECAYED OR DEAD PLANT MATERIAL. WARRANTY IS VOID IF PLANT MATERIAL ARE UNDER OR OVER-WATERED/FERTILIZED, DAMAGED BY VANDALISM OR NEGLECTED BY OWNER AFTER FINAL MAINTENANCE PERIOD AND FINAL ACCEPTANCE IS PROVIDED.
 - REMOVE ALL TREE STAKING MATERIALS AT END OF WARRANTY, PRIOR TO FINAL ACCEPTANCE
- MAINTENANCE: THE OWNER OF THIS PROPERTY AND ANY FUTURE OWNERS SHALL BE RESPONSIBLE FOR THE PROPER LANDSCAPE AND IRRIGATION MAINTENANCE OF THIS SITE AND ANY RIGHT OF WAY AREAS BETWEEN THE CURB AND PROPERTY LINES OF THIS SITE. MAINTENANCE OF THIS SITE INCLUDES, BUT IS NOT LIMITED TO, IRRIGATION INSPECTIONS AND ADJUSTMENTS, IRRIGATION SYSTEM SHUT DOWN AND START UP, IRRIGATION LEAK REPAIR, LANDSCAPE WEEDING, MOWING, SEEDING, FERTILIZATION, WOOD MULCH AND ROCK COVER REPLACEMENT, PRUNING, AND PLANT MATERIAL REPLACEMENT (INCLUDING ANNUAL BEDS). ALL MAINTENANCE SHOULD BE IN ACCORDANCE WITH STANDARDS SPECIFIED WITHIN THE "ALCC SPECIFICATIONS HANDBOOK" REVISED EDITION, 1996. OWNER SHOULD CONTACT LANDSCAPE CONTRACTOR OR LANDSCAPE ARCHITECT REGARDING ANY QUESTIONS RELATING TO THE LANDSCAPE OR IRRIGATION MAINTENANCE OF THIS SITE.

EXISTING TREES
EXISTING TREES DESIGNATED ON PLANS AS "TO REMAIN", OR MARKED FOR PROTECTION AND PRESERVATION IN THE FIELD, SHALL NOT BE REMOVED OR DAMAGED.

NO GRADING TO OCCUR WITHIN THE CRITICAL ROOT ZONE / DRIP LINE OF EXISTING TREES. ALL GRADING AROUND EXISTING TREES TO REMAIN SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT.

PRIOR TO CONSTRUCTION, ALL PROTECTED TREES SHALL HAVE ORANGE PROTECTION BARRIER FENCING ERECTED AT A HEIGHT OF 3' OR GREATER. FENCING TO BE SUPPORTED BY STURDY STOKK. CAPABLE OF SUPPORTING FENCING UNTIL ALL CONSTRUCTION OPERATIONS ARE COMPLETED. PLACE NO CLOSER THAN 6" FROM TRUNK, OR ONE HALF (1/2) OF THE DRIP LINE, WHICHEVER IS GREATER. WITHIN THE PROTECTED ZONE THERE SHALL BE NO MOVEMENT OF EQUIPMENT OR STORAGE OF EQUIPMENT, MATERIALS, WAIST, DEBRIS, OR FILL, UNLESS APPROVED BY THE LANDSCAPE ARCHITECT.

AVOID CUTTING SURFACE ROOTS WHEREVER POSSIBLE. SIDEWALKS AND PAVING LEVELS SHOULD BE CONTOURED SUFFICIENTLY TO AVOID SUCH. ROOT CUTS FROM EXCAVATION SHOULD BE DONE RAPIDLY. SMOOTH FLUSH CUTS SHOULD BE MADE. BACKFILL BEFORE ROOTS HAVE A CHANCE TO DRY OUT, AND THOROUGHLY WATER THE TREE IMMEDIATELY.

IRRIGATION NOTES

ALL TURF AREAS TO BE IRRIGATED WITH AN AUTOMATIC POP-UP SPRINKLER SYSTEM. ALL SHRUBS BEDS TO BE IRRIGATED WITH AUTOMATIC DRIP IRRIGATION SYSTEM. THE IRRIGATION SYSTEM IS TO BE ADJUSTED TO MEET THE NEEDS OF INDIVIDUAL PLANT MATERIAL.

IRRIGATION SYSTEM TO BE ADJUSTED AS NEEDED FOR PLANT ESTABLISHMENT FOR A PERIOD OF AT LEAST ONE (1) YEAR.

ADJUSTMENTS TO BE MADE AFTER ESTABLISHMENT BASED ON SPECIFIC PLANT REQUIREMENTS. SEE SUGGESTED RUN TIMES PROVIDED WITHIN THESE PLANS.

DESIGN OF IRRIGATION SYSTEMS TO MEET OR EXCEED LOCAL REQUIREMENTS AND INDUSTRY STANDARDS. CONSTRUCTION DOCUMENTS SUITABLE FOR DEVELOPMENT COORDINATION TO BE PROVIDED.

IRRIGATION SYSTEM TO BE DESIGNED USING APPROPRIATE COMPONENTS FOR PLANT MATERIAL, AND WILL INCLUDE A SMART ET CONTROLLER AND RAIN SENSOR.

ALL NATIVE SEED AREAS TO BE PERMANENTLY IRRIGATED.

PLAN NOTES:

- DEVELOPER WILL INSTALL ALL PRIVACY FENCING, TREES AND IRRIGATION IN THE LANDSCAPE BUFFERS. LANDSCAPE BUFFERS WILL BE OWNED AND MAINTAINED BY A COMMON OWNERS ASSOCIATION. FENCING, LANDSCAPING AND IRRIGATION ON THE INDIVIDUAL LOTS WILL BE THE RESPONSIBILITY EACH LAND OWNER AS THE LOTS ARE DEVELOPED.
- NO SUBSTITUTIONS WITHOUT PREVIOUS APPROVAL OF LANDSCAPE ARCHITECT. UNAPPROVED DEVIATIONS FROM THIS PLAN WILL BE RECTIFIED AT CONTRACTORS EXPENSE. THIS INCLUDES DEVIATIONS OF CULTIVARS FROM THOSE PROPOSED. SEE NOTE #11 FOR ID TAG RETENTION REQUIREMENTS.
- CONTRACTOR TO PROVIDE ANALYSIS OF ANY AMENDMENTS PROPOSED FOR PLANTING AREAS PRIOR TO INSTALLATION OF SUCH MATERIALS.
- CONTRACTOR TO PROVIDE RECEIPTS TO LANDSCAPE ARCHITECT FOR ALL SEEDING PROPOSED ON SITE, PRIOR TO INSTALLATION OF SEEDING MATERIALS.
- NO FABRIC UNDER WOOD MULCH IN ANY AREAS. ALL PLANTS IN ROCK MULCH AREAS TO RECEIVE SHREDDED CEDAR MULCH RINGS. MASSING SHALL HAVE CONTINUOUS SHREDDED MULCH BANDS. SEE DETAILS SHEET L2.0.
- DRIPLINE TO BE PLACED OVER WEED BARRIER FABRIC AND STAKED ON TOP OF WEED BARRIER.
- WEED BARRIER CUTOUTS FOR PLANTS IN ROCK AREAS SHALL ACCOUNT FOR MATURE SIZE OF PLANTS AND EQUAL AT LEAST THE DIAMETER OF THE ROOTBALL. SEE DETAIL SHEET L2.0
- ALL EMITTERS PER IRRIGATION PLAN.
- ALL EMITTERS TO BE PLACED AT THE APPROPRIATE LOCATIONS. ALL EMITTERS TO USE MICRO TUBING, STAKES, AND BUG CAPS.
- SEE LANDSCAPE DETAILS SHEET FOR ADDITIONAL NOTES AND DETAILS.
- RETAIN 10% OF ALL PLANT TAGS PER SPECIES FOR DURATION OF WARRANTY PERIOD.

EXISTING TREE PROTECTION DIRECTIONS:

PROTECTIVE FENCING:

FOUR FEET HEIGHT PROTECTIVE FENCING IS TO BE INSTALLED AROUND THE EXISTING TREES TO REMAIN PRIOR TO CONSTRUCTION ON THIS SITE. CONTRACTOR IS TO TAKE PRECAUTIONS TO ENSURE THAT EXISTING ROOTS AND LIMBS ARE NOT DAMAGED DURING EXCAVATION ADJACENT TO TREES. FENCING IS TO BE INSTALLED BELOW THE EDGE OF THE CANOPY OF THE EXISTING TREES TO REMAIN. FENCING IS TO REMAIN IN PLACE FOR THE DURATION OF CONSTRUCTION.


IF ROOT PRUNING IS NECESSARY FOR GRADING, EXCAVATING, OR INSTALLATION OF IRRIGATION SYSTEM, ALL ROOT PRUNING IS TO TAKE PLACE OUTSIDE OF THE PROTECTIVE FENCING AROUND EACH TREE. CONTRACTOR IS TO TRENCH 12" AWAY FROM PROTECTIVE FENCING. ANY ROOTS LARGER THAN 2" ARE TO BE SAW CUT. CONTRACTOR IS TO HAND DIG ANY TRENCHES AND SAW CUT ANY INTERFERING ROOTS INSIDE THE PROTECTIVE FENCE AREAS.

WATERING, MULCHING, AND FERTILIZATION:

PRIOR TO CONSTRUCTION CONTRACTOR IS TO PLACE A 4" DEPTH OF WOOD CHIPS OR MULCH INSIDE THE PROTECTIVE FENCING OF EXISTING TREES TO REMAIN. CONTRACTOR IS TO PROVIDE REGULAR DEEP WATERING TO ALL EXISTING TREES TO REMAIN THROUGHOUT CONSTRUCTION. DURING CONSTRUCTION A SLOW-RELEASE NITROGEN FERTILIZER IS TO BE APPLIED AROUND THE BASE OF EACH TREE AT A RATE OF 2 LBS. PER 1000 S.F. (USE DRIP LINE OF TREE TO CALCULATE SQUARE FOOTAGE).



EXISTING TREE PROTECTION DETAIL



Use trees spade to relocate trees. Preserve the rootball and existing roots. Deep water for three months, provide drip irrigation thereafter.

REVISIONS:



NO.	REVISION	DATE	BY
1	INITIAL RELEASE	06/25/21	CFC

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602) 264-7263 ext. 233

HIGH PLAINS BANK
KEENESBURG, CO

FINAL LANDSCAPE PLAN DETAILS & NOTES

PROJ. NO.:	05.31.21
DATE:	05.31.21
SCALE:	See Sheet
DRAWN:	JRO
CHKD BY:	NAM
SHEET	L2.0

127 S. DENVER AVE
FT. LUTPON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc L.L.C.

LANDSCAPE PLAN
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN OF KEENESBURG, WELD COUNTY, COLORADO

DigiSafely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0027-LAND
SHEET
27 OF 28



High Plains Bank
Keenesburg, CO

DATE: 6.23.2021
VERSION: Rendering

APPROVED BY:

SIGNATURE

DATE



High Plains Bank
Keenesburg, CO

DATE: 6.23.2021
VERSION: Rendering

APPROVED BY:

SIGNATURE

DATE




High Plains Bank
Keenesburg, CO

DATE: 6.23.2021
VERSION: Rendering

APPROVED BY:

SIGNATURE

DATE



FLOOR PLAN
SCALE: 1/8" = 1'-0"

High Plains Bank
Keenesburg, CO

DATE: 6.23.2021
VERSION: 003

APPROVED BY:

SIGNATURE

DATE



127 S. DENVER AVE
FT. LUTON, CO 80621
www.westerneci.com
email@westerneci.com
(720) 685-9951
FAX (720) 294-1330

Western Engineering Consultants, Inc. LLC

NO.	DATE	BY	REVISION	INITIAL	DATE	BY
1	06/25/21	CFC	INITIAL RELEASE			

DBSI + CFM

CONTACT: BRIAN SILVESTER
6950 W MORELOS PL
CHANDLER, AZ 85226
(602)264-7263 ext. 233

BUILDING RENDERINGS
MARKET STREET BUSINESS
PARK SUBDIVISION - LOT 2
TOWN of KEENESBURG, WELD COUNTY, COLORADO

Dig Safely.
CALL UNCC
THREE WORKING DAYS
BEFORE YOU DIG
811
www.uncc.org
UTILITY NOTIFICATION
CENTER OF COLORADO

ONLY VALID FOR CONSTRUCTION
IF SEAL & ORIGINAL SIGNATURE
ARE ON EACH SHEET

INITIAL PLAN
RELEASE: 06/25/21
DESIGNED BY: CFC
DRAWN BY: CFC
CHECKED BY: CFC
PROJECT NO.
01-0355.001.02
DOC CON #
0028-BLDG
SHEET
28 OF 28